COOK COUNTY (SOUTH)	SIGN PANEL TYPE 2				SIGN PANEL TYPE 1																					
	DO NOT ENTER (R5-1)		KEEP RIGHT (R4-7)		INTERSTATE 2 DIGITS (M1-1)		CARDINAL DIRECTION (M3-1,2,3,4)		DIRECTIONAL ARROW (M6-2A)		WRONG WAY (R5-1A)		ONE WAY (R6-1L)		ONE WAY (R6-1R)		NO RIGHT TURN (R3-1)		NO LEFT TURN (R3-2)		RETROREFLECTIVE SIGN SUPPORT PANEL		TELESCOPING STEEL SIGN SUPPORT		BASE FOR TELESCOPING STEEL SIGN SUPPORT	REMOVE SIGN ASSEMBLY TYPE A	REMOVE SIGN ASSEMBLY TYPE B	REMOVE SIGN PANEL TYPE 1
	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY/TOTAL FT		(EA)	(EA)	(EA)	(SQ FT)
NB IL 394 TO GLENWOOD DYER RD (LOC. 1)	2	32	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	1	9	6	5.00	7	110	1	2	0	0
SB IL 394 TO GLENWOOD DYER RD (LOC. 1)	2	32	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	1	9	6	5.00	7	110	1	1	0	9
NB I-57 TO VOLLMER RD (LOC. 2)	0	0	0	0	0	0	0	0	0	0	2	17.5	0	0	0	0	0	0	0	0	2	1.67	2	30	0	0	0	0
NB I-57 TO US RTE 30 (LINCOLN HWY) (LOC. 3)	0	0	0	0	0	0	0	0	0	0	2	17.5	0	0	0	0	0	0	1	9	2	1.67	3	40	1	0	0	0
SB I-57 TO SAUK TRAIL (LOC. 4)	0	0	0	0	0	0	0	0	0	0	2	17.5	1	6.75	1	6.75	0	0	0	0	6	5.00	6	100	0	2	0	0
NB I-57 TO SAUK TRAIL (LOC. 4)	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	4	3.33	4	65	0	1	0	0
SB US RTE 45 TO IL RTE 83 (CALUMET SAG RD) (LOC. 5)	2	32	1	20	0	0	0	0	0	0	4	35	2	13.5	2	13.5	0	0	0	0	8	6.67	10	144	4	1	0	9
NB US RTE 45 TO IL RTE 83 (CALUMET SAG RD) (LOC. 5)	2	32	0	0	0	0	0	0	0	0	4	35	2	13.5	2	13.5	0	0	0	0	8	6.67	8	120	2	0	0	9
I-80/94 TO US RTE 6/IL RTE 83(TORRENCE AVE) (LOC. 6)	5	80	0	0	4	36	2	9	2	8.75	8	70	2	13.5	2	13.5	0	0	0	0	22	18.33	16	174	15	1	0	0
EB I-80 TO KEDZIE AVE (LOC. 7)	2	32	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	8	6.67	6	90	2	3	0	0
SB I-94 (BISHOP FORD FRWY) TO DOTY AVE (137TH ST) (LOC. 8)	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	6	5.00	6	100	0	2	0	0
* ~~SB I-294 (TRI-STATE TOLLWAY) TO 127TH ST (LOC. 9)~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0.00~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~
* ~~NB I-294 (TRI-STATE TOLLWAY) TO 127TH ST (LOC. 9)~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0.00~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~
* ~~NB I-294 (TRI-STATE TOLLWAY) TO US RTE 12 (95TH ST) (LOC. 10)~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0.00~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~	~~0~~
TOTAL	15	240	1	20	4	36	2	9	2	8.75	32	280	17	114.8	17	114.8	0	0	3	27	78	65.00	75	1083	26	13	0	27

*** LOCATIONS NO. 9 AND 10 ELIMINATED**

NOTE:
RETROREFLECTIVE SIGN PANEL SHALL BE USED ON SIGN SUPPORTS
FOR 'DO NOT ENTER' AND 'WRONG WAY' SIGNS

1 Rev. Sheet 7-17-13

FILE NAME = c:\pw_work\pwidot\smithcj\d0348446\Design-ent-RampSignage-DuPageCo.dgn	USER NAME = SMITHCJ	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 7/9/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

COOK COUNTY (SOUTH)
SIGN SCHEDULE OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	2013-025-SG	COOK/WILL	57	7
		CONTRACT NO. 60W51		
	ILLINOIS FED. AID PROJECT			