

ROUTE: Palatine Rd. (Kennicott Blvd. to Arlington Heights Rd.)							
CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Arlington Heights Rd		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	3	12	3	36	4
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	3	12	3	6	1
		WB	INT	20	3	60	7
		WB	INT	20	3	60	7
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	3	12	3	6	1
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	1	12	6	72	8
		WB	1	12	3	6	1
		WB	1,2	2	150	1800	200
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	2	50	100	11
		WB	2	2	450	900	100
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	12	3	36	4
		WB	2	2	100	200	22
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	1	12	3	36	4
		WB	2	12	3	36	4
		WB	1	12	5	60	7
		WB	2	12	5	60	7
		WB	2	12	3	36	4
		WB	LTL	12	3	36	4
		WB	LTL	12	3	36	4
		WB	INT	2	100	200	22
		WB	1	12	3	36	4
	Kennicott Blvd	WB	LTL	2	100	200	22
Kennicott Blvd		EB	INT	2	100	1200	133
		EB	1	12	3	36	4
		EB	2	12	3	36	4
		EB	1	12	3	36	4
		EB	2	12	3	36	4
		EB	1	12	3	36	4
		EB	2	12	3	36	4
		EB	1	12	3	36	4
		EB	2	12	3	36	4
		EB	1	12	3	36	4
		EB	2	12	3	36	4
		EB	1	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4
		EB	2	12	3	36	4

ROUTE: Palatine Rd. (Kennicott Blvd. to Arlington Heights Rd.)								(Continued)
CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR	
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA	
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)	
		EB	1,2	2	60	120	13	
		EB	1	12	3	36	4	
		EB	2	12	3	36	4	
		EB	1	12	5	60	7	
		EB	1	12	3	36	4	
		EB	1	12	6	72	8	
		EB	1	12	3	36	4	
		EB	2	12	3	36	4	
		EB	1	12	3	36	4	
		EB	2	12	3	36	4	
		EB	3	12	3	36	4	
		EB	1	12	3	36	4	
		EB	2	12	3	36	4	
		EB	3	12	3	36	4	
		EB	1	12	3	36	4	
		EB	2	12	3	36	4	
	Arlington Heights Rd	EB	3	12	3	36	4	
				TOTALS:		1320	800	
						FT	SY	

ROUTE: Arlington Heights Rd. (Rand Rd. to Thomas St.)							
CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Thomas St		NB	INT	3	70	210	23
		NB	1	12	3	36	4
		NB	2	12	3	36	4
		NB	1	12	3	36	4
		NB	2	12	3	36	4
		NB	2	12	5	60	7
		NB	INT	3	100	300	33
		NB	1	12	3	36	4
		NB	2	12	3	36	4
		NB	1	12	3	36	4
	Lillian Ave	NB	2	12	3	36	4
Lillian Ave	Palatine Rd	NB	RTL	12	15	180	20
Palatine Rd		NB	1,2	2	15	30	3
		NB	1	12	3	36	4
		NB	2	12	3	36	4
		NB	1	12	3	36	4
		NB	2	12	3	36	4
		NB	1	12	3	36	4
		NB	2	12	3	36	4
		NB	1	12	6	72	8
		NB	1	12	3	36	4
		NB	2	12	3	36	4
		NB	1	12	3	36	4
		NB	2	12	3	36	4
		NB	1	12	3	36	4
		NB	LTL	12	3	36	4
		NB	2	12	3	36	4
		NB	1	12	3	36	4

CONTINUED ON NEXT SHEET

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
es:\pwork\pwork\teriqf\0335178\HMA-000-NORTH-Design.dgn	teriqf	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INTERMITTENT RESURFACING SCHEDULE
PALATINE RD. AND ARLINGTON HEIGHTS RD.**

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2013-032 RS	COOK	37	25
			CONTRACT NO. 60W68	
ILLINOIS FED. AID PROJECT				