

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1					
40600300	AGGREGATE (PRIME COAT)	TON	5	5					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	63	63					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, "F", N90	TON	235	235					
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	2092	2092					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1					
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	73	73					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	24	24					
* SPECIALTY ITEM									

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	800	800					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	225	225					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	225	225					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	98	98					
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1					
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
* SPECIALTY ITEM									

FILE NAME: C:\p\work\temp\p03357\B\HWA L50.dgn	USER NAME: Pencil	DESIGNED: -	REVISED: -
		DRAWN: -	REVISED: -
		CHECKED: -	REVISED: -
		DATE: -	REVISED: -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.

F.A.P. RTE. 341	SECTION 2013-042PP	COUNTY COOK	TOTAL SHEETS 12	SHEET NO. 3
CONTRACT NO. 60W89				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				