

SCHEDULE OF QUANTITIES

F.A.I. 57

I-57 SOUTHBOUND CLASS A PATCHES 13"											
COUNTY	RURAL/ URBAN	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA		SAW CUTS (FT)	PATCHING REINFORCEMENT (SQ YD)
								TYPE II 13.0" 44200610 (SQ YD)			
CHAMPAIGN	RURAL	251+67.55	230.667	SOUTHBOUND	DL	6	12	8.0		60.0	8.0
CHAMPAIGN	RURAL	251+67.55	230.667	SOUTHBOUND	PL	6	12	8.0		60.0	8.0
TOTALS =								16.0		120.0	16.0
CHAMPAIGN CO. I-57 RURAL TOTALS =								16.0		120.0	16.0
USE =								16.0		120.0	16.0

I-57 NORTHBOUND CLASS B PATCHES 15"														
COUNTY	RURAL/ URBAN	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA				SAW CUTS (FT)	TIE BARS 3/4" (EACH)	PAVEMENT FABRIC (SQ YD)
								TYPE II 15.0" 44201031 (SQ YD)	TYPE III 15.0" 44201035 (SQ YD)	TYPE IV 15.0" 44201037 (SQ YD)	BARS 1 1/2" 44201299 (EACH)			
CHAMPAIGN	RURAL	367+49.76	224.467	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	RURAL	367+86.72	224.474	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	RURAL	368+34.24	224.483	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	RURAL	368+50.08	224.486	NORTHBOUND	DL	12	12		16.0		20	60.0		16.0
CHAMPAIGN	RURAL	472+51.68	226.456	NORTHBOUND	PL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	354+89.95	232.622	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	354+89.95	232.622	NORTHBOUND	PL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	431+01.61	234.064	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	433+86.73	234.118	NORTHBOUND	DL	8	12	10.7			20	52.0		
CHAMPAIGN	URBAN	486+93.13	235.123	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	486+93.13	235.123	NORTHBOUND	PL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	527+42.89	235.890	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	528+43.21	235.909	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	533+60.65	236.007	NORTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	534+02.89	236.015	NORTHBOUND	DL	6	12	8.0			20	48.0		
SUB-TOTALS =								114.7	16.0		300.0	736.0		16.0

I-57 SOUTHBOUND CLASS B PATCHES 15"														
COUNTY	RURAL/ URBAN	STATION	MILEPOST	DIRECTION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA				SAW CUTS (FT)	TIE BARS 3/4" (EACH)	PAVEMENT FABRIC (SQ YD)
								TYPE II 15.0" 44201031 (SQ YD)	TYPE III 15.0" 44201035 (SQ YD)	TYPE IV 15.0" 44201037 (SQ YD)	BARS 1 1/2" 44201299 (EACH)			
CHAMPAIGN	RURAL	417+60.48	225.416	SOUTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	RURAL	417+60.48	225.416	SOUTHBOUND	PL	6	12	8.0			20	48.0		
CHAMPAIGN	RURAL	519+61.44	227.348	SOUTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	RURAL	106+47.55	227.917	SOUTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	RURAL	106+47.55	227.917	SOUTHBOUND	PL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	402+13.45	233.517	SOUTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	402+13.45	233.517	SOUTHBOUND	PL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	402+39.85	233.522	SOUTHBOUND	DL	30	12		40.0		30	96.0	15	40.0
CHAMPAIGN	URBAN	405+09.13	233.573	SOUTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	405+09.13	233.573	SOUTHBOUND	PL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	413+06.41	233.724	SOUTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	470+72.17	234.816	SOUTHBOUND	DL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	470+72.17	234.816	SOUTHBOUND	PL	6	12	8.0			20	48.0		
CHAMPAIGN	URBAN	485+71.69	235.100	SOUTHBOUND	PL	6	12	8.0			20	48.0		
SUB-TOTALS =								104.0		40.0	290.0	720.0	15.0	40.0
TOTALS =								218.7	16.0	40.0	590.0	1,456.0	15.0	56.0
CHAMPAIGN CO. I-57 RURAL TOTALS =								72.0	16.0		200.0	492.0		16.0
CHAMPAIGN CO. I-57 URBAN TOTALS =								147.0		40.0	390.0	964.0	15.0	40.0
USE =								219.0	16.0	40.0	590.0	1,456.0	15.0	56.0