

# SCHEDULE OF QUANTITIES

## PAVEMENT MARKING (SHEET 2 OF 2)

LINE/SD	LOCATION	STATION	TO	STATION	LENGTH (FOOT)	STRIPE WIDTH (INCH)	MODIFIED URETHANE PAVEMENT MARKING - LINE, 4" 78009004 (FOOT)		PAVEMENT REMOVAL 78300100 (SQ FT)
							YELLOW	WHITE	
SD	NB INSIDE LL	279+25.00		299+21.51	1,996.51	4.0	0.0	499.1	166.4
SD	NB INSIDE LL	300+51.28		305+32.76	481.48	4.0	0.0	120.4	40.1
SD	NB INSIDE LL	307+66.28		312+44.15	477.87	4.0	0.0	119.5	39.8
SD	NB INSIDE LL	314+36.18		327+50.47	1,314.29	4.0	0.0	328.6	109.5
SD	NB INSIDE LL	328+77.14		340+63.13	1,185.99	4.0	0.0	296.5	98.8
SD	NB INSIDE LL	341+45.35		354+34.39	1,289.04	4.0	0.0	322.3	107.4
SD	NB INSIDE LL	355+18.37		379+09.24	2,390.87	4.0	0.0	597.7	199.2
SD	NB INSIDE LL	380+45.32		392+10.00	1,164.68	4.0	0.0	291.2	97.1
SD	NB INSIDE LL	392+00.00		394+98.51	298.51	4.0	0.0	74.6	24.9
SD	NB OUTSIDE LL	279+25.00		299+21.51	1,996.51	4.0	0.0	499.1	166.4
SD	NB OUTSIDE LL	300+51.28		305+41.98	490.70	4.0	0.0	122.7	40.9
SD	NB OUTSIDE LL	307+77.03		312+44.15	467.12	4.0	0.0	116.8	38.9
SD	NB OUTSIDE LL	314+36.18		327+50.47	1,314.29	4.0	0.0	328.6	109.5
SD	NB OUTSIDE LL	328+77.14		340+63.13	1,185.99	4.0	0.0	296.5	98.8
SD	NB OUTSIDE LL	341+45.35		354+34.39	1,289.04	4.0	0.0	322.3	107.4
SD	NB OUTSIDE LL	355+18.37		379+09.24	2,390.87	4.0	0.0	597.7	199.2
SD	NB OUTSIDE LL	380+45.32		392+10.00	1,164.68	4.0	0.0	291.2	97.1
SD	NB OUTSIDE LL	392+00.00		395+10.25	310.25	4.0	0.0	77.6	25.9
Y LINE	NB EL	282+80.81		291+66.02	885.21	4.0	885.2	0.0	295.1
W LINE	NB OLTL	293+39.27		299+21.51	582.24	4.0	0.0	582.2	194.1
W LINE	NB OLTL	307+57.82		312+44.15	486.33	4.0	0.0	486.3	162.1
Y LINE	NB EL	320+21.55		321+02.99	81.44	4.0	81.4	0.0	27.1
W LINE	NB OLTL	322+95.31		327+32.27	436.96	4.0	0.0	437.0	145.7
W LINE	NB OLTL	335+22.35		340+63.13	540.78	4.0	0.0	540.8	180.3
Y LINE	NB EL	341+70.41		349+44.29	773.88	4.0	773.9	0.0	258.0
W LINE	NB OLTL	351+39.80		354+34.39	294.59	4.0	0.0	294.6	98.2
Y LINE	NB EL	355+94.06		364+62.59	868.53	4.0	868.5	0.0	289.5
W LINE	NB OLTL	376+57.51		379+09.24	251.73	4.0	0.0	251.7	83.9
SD	NB ILTL	293+39.27		298+74.53	535.26	4.0	0.0	133.8	44.6
SD	NB ILTL	322+95.31		327+09.75	414.44	4.0	0.0	103.6	34.5
SD	NB ILTL	351+39.80		353+89.37	249.57	4.0	0.0	62.4	20.8
W LINE	NB RTL	293+39.27		299+08.98	569.71	4.0	0.0	569.7	189.9
W LINE	NB RTL	307+87.76		312+44.95	457.19	4.0	0.0	457.2	152.4
W LINE	NB RTL	322+95.31		327+32.27	436.96	4.0	0.0	437.0	145.7
W LINE	NB RTL	335+22.35		340+54.00	531.65	4.0	0.0	531.7	177.2
W LINE	NB RTL	351+39.80		354+25.45	285.65	4.0	0.0	285.6	95.2
W LINE	NB RTL	374+65.89		379+09.24	443.35	4.0	0.0	443.3	147.8
SUB-TOTAL (SHEET 1) =							2,609.1	10,919.1	4,509.4

LL = LANE LINE  
 OLTL = OUTSIDE LEFT TURN LANE  
 ILTL = INSIDE LEFT TURN LANE  
 RTL = RIGHT TURN LANE  
 EL = EDGELINE  
 SD = SKIP DASH

LINE/SD	LOCATION	STATION	TO	STATION	LENGTH (FOOT)	STRIPE WIDTH (INCH)	MODIFIED URETHANE PAVEMENT MARKING - LINE, 4" 78009004 (FOOT)		PAVEMENT REMOVAL 78300100 (SQ FT)
							YELLOW	WHITE	
SD	SB INSIDE LL	279+25.00		298+84.04	1,959.04	4.0	0.0	489.8	163.3
SD	SB INSIDE LL	300+31.52		304+92.92	461.40	4.0	0.0	115.3	38.4
SD	SB INSIDE LL	307+25.95		312+44.15	518.20	4.0	0.0	129.6	43.2
SD	SB INSIDE LL	313+96.44		327+09.75	1,313.31	4.0	0.0	328.3	109.4
SD	SB INSIDE LL	326+46.78		340+07.31	1,360.53	4.0	0.0	340.1	113.4
SD	SB INSIDE LL	341+36.42		353+73.71	1,237.29	4.0	0.0	309.3	103.1
SD	SB INSIDE LL	355+72.60		379+09.24	2,336.64	4.0	0.0	584.2	194.7
SD	SB INSIDE LL	380+45.32		392+10.00	1,164.68	4.0	0.0	291.2	97.1
SD	SB INSIDE LL	392+00.00		394+72.09	272.09	4.0	0.0	68.0	22.7
SD	SB OUTSIDE LL	279+25.00		298+84.04	1,959.04	4.0	0.0	489.8	163.3
SD	SB OUTSIDE LL	300+31.52		304+83.67	452.15	4.0	0.0	113.0	37.7
SD	SB OUTSIDE LL	307+16.70		312+44.15	527.45	4.0	0.0	131.9	44.0
SD	SB OUTSIDE LL	313+96.44		327+09.75	1,313.31	4.0	0.0	328.3	109.4
SD	SB OUTSIDE LL	328+46.78		340+07.31	1,160.53	4.0	0.0	290.1	96.7
SD	SB OUTSIDE LL	341+36.42		353+73.71	1,237.29	4.0	0.0	309.3	103.1
SD	SB OUTSIDE LL	355+72.60		377+78.50	2,205.90	4.0	0.0	551.5	183.8
SD	SB OUTSIDE LL	380+45.32		392+10.00	1,164.68	4.0	0.0	291.2	97.1
SD	SB OUTSIDE LL	392+00.00		394+60.35	260.35	4.0	0.0	65.1	21.7
W LINE	SB OLTL	279+25.00		282+46.75	321.75	4.0	0.0	321.8	107.3
Y LINE	SB EL	284+44.46		292+86.81	842.35	4.0	842.4	0.0	280.8
W LINE	SB OLTL	300+31.52		304+58.04	426.52	4.0	0.0	426.5	142.2
Y LINE	SB EL	307+34.45		312+44.15	509.70	4.0	509.7	0.0	169.9
W LINE	SB OLTL	313+96.44		319+73.79	577.35	4.0	0.0	577.4	192.5
Y LINE	SB EL	322+03.45		322+95.31	91.86	4.0	91.9	0.0	30.6
W LINE	SB OLTL	328+46.78		332+92.69	445.91	4.0	0.0	445.9	148.6
Y LINE	SB EL	335+22.35		340+07.31	484.96	4.0	485.0	0.0	161.7
W LINE	SB OLTL	341+36.42		346+67.36	530.94	4.0	0.0	530.9	177.0
Y LINE	SB EL	348+97.02		350+98.29	201.27	4.0	201.3	0.0	67.1
W LINE	SB OLTL	355+72.60		359+17.35	344.75	4.0	0.0	344.8	114.9
Y LINE	SB EL	361+47.08		366+50.27	503.19	4.0	503.2	0.0	167.7
W LINE	SB OLTL	380+45.32		385+12.49	467.17	4.0	0.0	467.2	155.7
SD	SB ILTL	279+25.00		282+46.75	321.75	4.0	0.0	80.4	26.8
SD	SB ILTL	300+62.96		304+58.04	395.08	4.0	0.0	98.8	32.9
SD	SB ILTL	314+48.51		319+73.79	525.28	4.0	0.0	131.3	43.8
SD	SB ILTL	328+88.48		332+92.69	404.21	4.0	0.0	101.1	33.7
W LINE	SB RTL	300+47.48		304+68.24	420.76	4.0	0.0	420.8	140.3
W LINE	SB RTL	314+73.78		319+73.79	500.01	4.0	0.0	500.0	166.7
W LINE	SB RTL	329+17.14		333+64.87	447.73	4.0	0.0	447.7	149.2
W LINE	SB RTL	342+12.79		346+67.36	454.57	4.0	0.0	454.6	151.5
W LINE	SB RTL	355+72.60		361+47.08	574.48	4.0	0.0	574.5	191.5
W LINE	SB RTL	380+45.32		383+09.16	263.84	4.0	0.0	263.8	87.9

SUB-TOTAL (SHEET 2) =			2,633.3	11,413.3	4,682.2
SUB-TOTAL (SHEET 1):			2,609.1	10,919.1	4,509.4
TOTAL =			5,242.4	22,332.5	
GRAND TOTAL =			27,574.9		9,191.6
ROUND TO:			27,580.0		9,200.0