SCHEDULE OF QUANTITIES

CLASS B PATCHING SCHEDULE, 9"

F.A.P. 719 / (U.S. 150)

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	44200956 TYPE II, 9" (SQ YD)	44200964 TYPE IV, 9" (SQ YD)	44201299 DOWEL BARS, 1 1/2" (EACH)	44213200 SAW CUTS (FT)	44213100 PAVEMENT FABRIC (SQ YD)	44213204 TIE BARS, 3/4" (EACH)
E.B.	142+21.00	6.00	11.00	7.33		18.00	51.00		
E.B.	149+00.00	10.00	11.00	12.22		18.00	63.00		
E.B.	166+94.00	6.00	11.00	7.33		18.00	51.00		
E.B.	167+80.00	6.00	11.00	7.33		18.00	51.00		
E.B.	167+93.00	6.00	11.00	7.33		18.00	51.00		
E.B.	168+23.00	6.00	11.00	7.33		18.00	51.00		
E.B.	168+41.00	6.00	11.00	7.33		18.00	51.00		
E.B.	168+93.00	8.00	11.00	9.78		18.00	57.00		
E.B.	169+92.00	6.00	11.00	7.33		18.00	51.00		
E.B.	170+93.00	6.00	11.00	7.33		18.00	51.00		
E.B.	171+05.00	6.00	11.00	7.33		18.00	51.00		
E.B.	171+93.00	6.00	11.00	7.33		18.00	51.00		
E.B.	173+95.00	6.00	11.00	7.33		18.00	51.00		
E.B.	174+94.00	6.00	11.00	7.33		18.00	51.00		
E.B.	175+94.00	6.00	11.00	7.33		18.00	51.00		
E.B.	176+94.00	6.00	11.00	7.33		18.00	51.00		
E.B.	178+10.00	6.00	11.00	7.33		18.00	51.00		
E.B.	178+92.00	6.00	11.00	7.33		18.00	51.00		
E.B.	179+94.00	6.00	11.00	7.33		18.00	51.00		
E.B.	181+93.00	6.00	11.00	7.33		18.00	51.00		
E.B.	183+94.00	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
E.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	142+21.00	6.00	11.00	7.33		18.00	51.00		
W.B.	166+94.00	6.00	11.00	7.33		18.00	51.00		
W.B.	167+93.00	6.00	11.00	7.33		18.00	51.00		
W.B.	168+23.00	6.00	11.00	7.33		18.00	51.00		
W.B.	168+41.00	6.00	11.00	7.33		18.00	51.00		
W.B.	168+93.00	8.00	11.00	9.78		18.00	57.00		
W.B.	169+92.00	6.00	11.00	7.33		18.00	51.00		
W.B.	173+95.00	6.00	11.00	7.33		18.00	51.00		
W.B.	174+94.00	6.00	11.00	7.33		18.00	51.00		
W.B.	175+46.00	6.00	11.00	7.33		18.00	51.00		
W.B.	175+78.00	25.00	11.00		30.56	27.00	108.00	30.56	25.00
W.B.	176+02.00	25.00	11.00		30.56	27.00	108.00	30.56	25.00
W.B.	176+34.00	25.00	11.00		30.56	27.00	108.00	30.56	25.00
W.B.	176+68.00	25.00	11.00		30.56	27.00	108.00	30.56	25.00
W.B.	176+95.00	6.00	11.00	7.33		18.00	51.00		
W.B.	177+15.00	6.00	11.00	7.33		18.00	51.00		
W.B.	177+30.00	6.00	11.00	7.33		18.00	51.00		
W.B.	177+44.00	6.00	11.00	7.33		18.00	51.00		
W.B.	177+59.00	6.00	11.00	7.33		18.00	51.00		
W.B.	177+76.00	6.00	11.00	7.33		18.00	51.00		
W.B.	177+93.00	6.00	11.00	7.33		18.00	51.00		
W.B.	178+26.00	6.00	11.00	7.33		18.00	51.00		
W.B.	178+38.00	6.00	11.00	7.33		18.00	51.00		
W.B.	178+52.00	6.00	11.00	7.33		18.00	51.00		
W.B.	178+68.00	6.00	11.00	7.33		18.00	51.00		
W.B.	178+79.00	6.00	11.00	7.33		18.00	51.00		
W.B.	178+88.00	6.00	11.00	7.33		18.00	51.00		
W.B.	179+00.00	6.00	11.00	7.33		18.00	51.00		
W.B.	179+83.00	6.00	11.00	7.33		18.00	51.00		

CLASS B PATCHING SCHEDULE, 9", CONTINUED

F.A.P. 719 / (U.S. 150)

LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	44200956 TYPE II, 9" (SQ YD)	44200964 TYPE IV, 9" (SQ YD)	44201299 DOWEL BARS, 1 1/2" (EACH)	44213200 SAW CUTS (FT)	44213100 PAVEMENT FABRIC (SQ YD)	44213204 TIE BARS, 3/4" (EACH)
W.B.	180+18.00	6.00	11.00	7.33		18.00	51.00		
W.B.	180+27.00	6.00	11.00	7.33		18.00	51.00		
W.B.	180+45.00	6.00	11.00	7.33		18.00	51.00		
W.B.	180+66.00	12.00	11.00	14.67		18.00	69.00		
W.B.	180+84.00	6.00	11.00	7.33		18.00	51.00		
W.B.	181+19.00	6.00	11.00	7.33		18.00	51.00		
W.B.	181+30.00	6.00	11.00	7.33		18.00	51.00		
W.B.	181+77.00	25.00	11.00		30.56	27.00	108.00	30.56	25.00
W.B.	182+15.00	6.00	11.00	7.33		18.00	51.00		
W.B.	182+30.00	6.00	11.00	7.33		18.00	51.00		
W.B.	182+43.00	6.00	11.00	7.33		18.00	51.00		
W.B.	182+61.00	6.00	11.00	7.33		18.00	51.00		
W.B.	182+97.00	6.00	11.00	7.33		18.00	51.00		
W.B.	183+11.00	8.00	11.00	9.78		18.00	51.00		
W.B.	183+26.00	6.00	11.00	7.33		18.00	51.00		
W.B.	183+37.00	6.00	11.00	7.33		18.00	51.00		
W.B.	183+48.00	6.00	11.00	7.33		18.00	51.00		
W.B.	183+65.00	6.00	11.00	7.33		18.00	51.00		
W.B.	183+94.00	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
W.B.	MISC	6.00	11.00	7.33		18.00	51.00		
CTL	177+95.00	6.00	11.00	7.33		18.00	51.00		
CTL	178+10.00	6.00	11.00	7.33		18.00	51.00		
CTL	178+92.00	6.00	11.00	7.33		18.00	51.00		
CTL	179+94.00	6.00	11.00	7.33		18.00	51.00		
CTL	183+94.00	6.00	11.00	7.33		18.00	51.00		
			TOTAL =	730.89	152.78	1881.00	5529.00	152.80	125.00
			USE =	731.00	153.00	1881.00	5529.00	153.00	125.00
				(SQ YD)	(SQ YD)	(EACH)	(FT)	(SQ YD)	(EACH)

PARTIAL DEPTH PAVEMENT PATCHING

F.A.P. 804 / (PROSPECT AVE.)

LOCATION	STATION	NUMBER OF PATCHES	44022039 PARTIAL DEPTH REMOVAL 5 1/2" (SQ YD)	X4421000 PARTIAL DEPTH PATCHING (TON)
RT. TURN LANE	MISC	1.00	150.00	46.20
		TOTAL =	150.00	46.20
		USE =	150.00	47.00
			(SQ YD)	(TON)

NOTE:

THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS.
THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED
IN G.N.-442B

* F.A.P. 719 & F.A.P. 804