

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				ROADWAY 0005 S.N.
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.7	6.7
40600300	AGGREGATE (PRIME COAT)	TON	35.5	35.5
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	26.6	26.6
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1,200.0	1,200.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	17,762	17,762
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	140	140
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	112	112
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	80	80
48101200	AGGREGATE SHOULDERS, TYPE B	TON	606.8	606.8
48203100	HOT-MIX ASPHALT SHOULDERS	TON	298	298
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	18	18
60100074	SHOULDER REMOVAL AND REPLACEMENT, 8"	FOOT	10,700	10,700
60108100	PIPE UNDERDRAINS, 4" (SPECIAL)	FOOT	360	360
60107600	PIPE UNDERDRAINS 4"	FOOT	10,700	10,700
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	10,700	10,700
67100100	MOBILIZATION	LSUM	1	1

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				ROADWAY 0005 S.N.
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	1065.6	1065.6
* 70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	11,989	11,989
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	178	178
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	11,989	11,989
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	70	70
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	70	70

PAVEMENT MARKING SCHEDULE			
STATION	TYPE	PAINT PAVEMENT MARKING - LINE 5"	
		WHITE	YELLOW
LT & RT STA. 323+14 TO 376+42.6	EDGE	10657	
STA. 323+14 TO 376+42.6	SKIP-DASH		1332
SUB-TOTAL		10657	1332
TOTAL		11989	

REVIS 6-5-13