



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 22, 2013

SUBJECT: FAP Route 331 (IL 13)
Project NHPP-0331 (066)
Section (1-4) R-2, N-4, TS-4
Williamson County
Contract No. 78258
Item No. 94, August 2, 2013 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions.
2. Revised pages 26-30 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Jeffrey Keirn, Region 5, District 9; Mike Renner; Estimates

INDUCTIVE LOOP DETECTOR, RACK MOUNTED 21

MASTER CONTROLLER..... 22

RADIO TRANSCEIVER 22

TRAFFIC SIGNAL POST SPECIAL..... 24

TRAFFIC SIGNAL COVER..... 24

HORIZONTAL TERMINAL COMPARTMENT AND CABLE TERMINATION..... 24

VERTICAL TYPE TERMINAL BLOCK AND HOUSING 25

MOWING..... 25

PIPE UNDERDRAIN REMOVAL (SPECIAL)..... 26

ANCHOR BOLTS (BDE) 30

BUILDING REMOVAL - CASE I (NON-FRIABLE AND FRIABLE ASBESTOS ABATEMENT) (BDE) 31

BUILDING REMOVAL - CASE II (NON-FRIABLE ASBESTOS ABATEMENT) (BDE) 34

BUILDING REMOVAL - CASE IV (NO ASBESTOS) (BDE)..... 37

ASBESTOS DRAWINGS 38

APPENDIX D 49

MONITORING WELL ABANDONMENT 52

CONCRETE BOX CULVERTS WITH SKEWS \leq 30 DEGREES REGARDLESS OF DESIGN FILL AND SKEWS $>$ 30 DEGREES WITH DESIGN FILLS $>$ 5 FEET (BDE) 52

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 53

FRICTION AGGREGATE (BDE) 62

GRANULAR MATERIALS (BDE)..... 65

GROOVING FOR RECESSED PAVEMENT MARKINGS (BDE)..... 66

MATERIAL TRANSFER DEVICE (BDE) 68

LIQUIDATED DAMAGES (BDE)..... 69

PAVEMENT MARKING REMOVAL (BDE) 69

PAVEMENT PATCHING (BDE)..... 70

PAVEMENT REMOVAL (BDE)..... 70

PAYMENTS TO SUBCONTRACTORS (BDE) 71

PLACING AND CONSOLIDATING CONCRETE (BDE)..... 72

PORTLAND CEMENT CONCRETE (BDE) 74

RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE) 113

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES 123

REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE) 129

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 130

SYNTHETIC FIBERS IN CONCRETE GUTTER, CURB, MEDIAN, AND PAVED DITCH (BDE)..... 130

TEMPORARY EROSION AND SEDIMENT CONTROL (BDE)..... 131

PIPE UNDERDRAIN REMOVAL (SPECIAL)

Description. This work shall consist of removing the existing pipe underdrain located approximately from IL 13 WB STA 473+60 LT to STA 480+37 LT. The existing underdrains may consist of 4" circular, 6" circular, or drainage mat underdrain. The underdrain travels along the existing shoulder parallel to IL 13 WB and outlets perpendicular at approximately STA 473+60 LT and STA 478+50 LT. The trench remaining from the pipe underdrain removal shall be backfilled with SUB-BASE GRANULAR MATERIAL, TYPE A in areas which are beneath proposed pavement and proposed shoulder. The SUBBASE GRANULAR MATERIAL, TYPE A shall not be paid for separately but shall be included in the cost of the pipe underdrain removal.

Method of Measurement: PIPE UNDERDRAIN REMOVAL (SPECIAL) will be measured for payment in feet along the invert of the pipe underdrain.

Basis of Payment: This work will be paid for at the contract unit price per foot for PIPE UNDERDRAIN REMOVAL (SPECIAL) which price shall include all costs for labor, materials, equipment, and incidentals necessary to perform the work. The removal of the pipe underdrain headwalls will be paid separately as CONCRETE HEADWALL REMOVAL.

Revised 7-22-13

This page intentionally left blank.

This page intentionally left blank.

Revised 7-22-13

This page intentionally left blank.

ANCHOR BOLTS (BDE)

Effective: January 1, 2013

Revise the fourth sentence of the first paragraph of Article 1006.09 of the Standard Specifications to read:

“Stud bolts or fully threaded rods shall be according to either ASTM A 354 Grade BC, ASTM A 193 Grade B7, or ASTM F 1554 Grade 105.”

Revised 7-22-13