

COUNTY:	WILLIAMSON
LOCATION:	URBAN
ROUTE:	F. A. P. 331 (IL 13)
FUNDING:	80% FEDERAL 20% STATE
WORK TYPE:	ROADWAY SAFETY
CONSTRUCTION TYPE CODE	0003 0021

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		
50104400	CONCRETE HEADWALL REMOVAL	EACH	11	11	
50105220	PIPE CULVERT REMOVAL	FOOT	1658	1658	
54001001	BOX CULVERT END SECTIONS CULVERT NO. 1	EACH	1	1	
54001002	BOX CULVERT END SECTIONS CULVERT NO. 2	EACH	1	1	
54001003	BOX CULVERT END SECTIONS CULVERT NO. 3	EACH	1	1	
54001004	BOX CULVERT END SECTIONS CULVERT NO. 4	EACH	1	1	
54010505	PRECAST CONCRETE BOX CULVERTS 5' X 5'	FOOT	8	8	
54010604	PRECAST CONCRETE BOX CULVERT 6' X 4'	FOOT	108	108	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	125	125	
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	61	61	
542A0247	PIPE CULVERTS, CLASS A, TYPE 1, 42"	FOOT	4	4	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	569	569	
54213450	END SECTIONS 15"	EACH	22	22	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	6	6	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	5	5	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	8	8	

1

1

17

1 REVISIED 6-5-13

FILE NAME : 0978258-shr-500-05.dgn
CH2MHILL

USER NAME : nfa	DESIGNED - KN	REVISED -
PLOT SCALE : 2.0000 / in.	DRAWN - AS	REVISED -
PLOT DATE : 3/11/2013	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 5 OF 16 SHEETS STA. TO STA.

F.A.P. RTE. 331	SECTION 11-41R-2, N-4, TS-4	COUNTY WILLIAMSON	TOTAL SHEETS 381	SHEET NO. 10
DRAWING NO. 500-05		CONTRACT NO. 78258		

ILLINOIS FED. AID PROJECT