



LEGEND	
(A)	EXISTING HMA PAVEMENT
(B)	PAVED SHOULDER REMOVAL
(C)	EXISTING HMA PAVEMENT TO BE MILLED
(1)	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N90, 1 1/2"
(2)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90, 2 1/2"
(3)	HOT-MIX ASPHALT SHOULDERS, 4"
(4)	AGGREGATE BASE COURSE, TYPE A 8"
(5)	HOT-MIX ASPHALT SHOULDERS, 15 1/4"
(6)	PIPE UNDERDRAINS, 4"
(7)	PROCESSING LIME STABILIZED SOIL MIXTURE 12"
(8)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24
(9)	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH
(10)	CONCRETE GUTTER, TYPE A (SPECIAL)
(11)	NOT USED
(12)	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N90, 2 1/2"
(13)	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH
(14)	CONCRETE GUTTER, TYPE A
(15)	AGGREGATE SHOULDERS, TYPE A 4"
(16)	CONCRETE MEDIAN SURFACE, 4 INCH
(17)	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)
(19)	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS
(20)	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 15 1/4"
(21)	SUBBASE GRANULAR MATERIAL, TYPE A 8"
(22)	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 10 3/4"
(23)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12
(24)	CONCRETE MEDIAN, TYPE SM-6.24
(25)	SUBBASE GRANULAR MATERIAL, TYPE A 12"
(26)	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24

- ① 11.6' AT STA 2+50.00 TO 12' AT STA 2+62.58
- ② 11.0' AT STA 2+50.00 TO 12' AT STA 2+79.47

NOTES:
 1. FOR ADDITIONAL WIDTH INFORMATION, SEE DRAWING ID-01.

FILE NAME =	USER NAME = moesbl	DESIGNED - KN	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED TYPICAL SECTIONS VENABLE DR, PLAZA DR EAST	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pwwork\pwwork\holl1e\bl\d0335666\0976258-shr-typical-20.dgn	PLOT SCALE = 10,0000' / 1"	DRAWN - AS	REVISED -			331	11-4R-2, N-4, TS-4	WILLIAMSON	381	41	
CH2MHILL	PLOT DATE = 6/26/2013	CHECKED -	REVISED -			DRAWING NO. TS-20		CONTRACT NO. 78258		ILLINOIS FED. AID PROJECT	
		DATE -	REVISED -			SCALE: NA	SHEET NO. 20 OF 21 SHEETS	STA.	TO STA.		