

## CURB AND GUTTER SCHEDULE

LOCATION			PROTECTIVE COAT	CONCRETE GUTTER, TYPE A	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	CONCRETE MEDIAN SURFACE 4"	CONCRETE MEDIAN, TYPE SM-6.24	CLASS SI CONCRETE (OUTLET)	REMARKS	
STATION	TO	STATION	SQ YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	CY		
<b>DIVISION STREET SOUTH</b>														
RT	1+02.83	-	1+55.52	25		86.0								
RT	2+49.06	-	4+50.12	58		201.0								
RT	5+60.69	-	12+43.43	241	724.0									
RT	12+43.43	-	16+91.90	149	448.0									
LT	0+95.98	-	1+18.82	22			76.5						SE QUADRANT ISLAND	
LT	0+95.98	-	1+18.82	34							308		SE QUADRANT ISLAND	
LT	0+98.38	-	2+81.11	65		226.0								
LT	2+98.22	-	4+77.17	52		180.5								
LT	2+81.11	-	2+98.22	13								3.4		
LT	4+77.17	-	5+16.19	17		58.5								
LT	6+26.77	-	8+66.50	69		240.0								
LT	8+66.50	-	12+80.00	144	431.0									
MED	1+24.78	-	5+04.94	258							775		CONCRETE MEDIAN, SM-6.24 HAS A 12" GUTTER PAN ADJACENT TO DUAL TURN LANES. FOR DETAILS, SEE DN. RD-01	
MED	1+29.18	-	5+00.94	107		374.5								
MED	1+29.18	-	5+00.94	107		374.5								
<b>NORTH FRONTAGE ROAD</b>														
RT	0+22.58	-	7+96.48	231		806.5								
RT	9+07.19	-	18+99.50	285		992.5								
RT	20+03.24	-	22+55.43	71		248.5								
LT	0+26.98	-	0+82.00	21		73.5								
LT	0+82.00	-	22+55.43	624		2,176.5								
<b>TIPPY ROAD</b>														
RT	8+69.64	-	9+74.55	35		120.5								
RT	8+60.11	-	8+69.64	12								3.6		
LT	8+04.71	-	9+74.70	53		186.5								
LT	7+97.71	-	8+04.75	8								3.1		
<b>LAKESHORE DRIVE</b>														
RT	0+12.63	-	1+50.00	44		152.0								
LT	0+16.69	-	1+50.00	43		150.5								
<b>KIRK LANE</b>														
RT	0+10.58	-	1+02.12	36		125.5								
RT	1+01.92	-	1+25.85	19								3.5		
LT	0+34.98	-	0+74.98	17		58.5								
LT	0+74.68	-	0+98.59	18								3.5		
<b>VENABLE DRIVE</b>														
RT	2+77.37	-	2+99.16	21								5.5		
RT	2+99.16	-	3+21.67	9	27.0									
LT	2+75.07	-	2+98.72	22								5.2		
LT	2+98.72	-	3+25.72	14	43.0									
<b>SHEET TOTALS</b>				<b>4024</b>	<b>1861.5</b>	<b>188.0</b>	<b>9929.0</b>	<b>156.5</b>	<b>0.0</b>	<b>0.0</b>	<b>320</b>	<b>1421</b>	<b>27.8</b>	