

PIPE UNDERDRAIN SCHEDULE

LOCATION			CONCRETE HEADWALLS FOR PIPE DRAINS EACH	PIPE UNDERDRAINS 4" FOOT	PIPE UNDERDRAINS 4" (SPECIAL) FOOT	REMARKS
STATION	TO	STATION				
IL 13 WESTBOUND						
441+90.26			1		22	
441+90.26	-	446+30.01		440		
446+30.01	-	451+66.74		537	10	OUTLET INTO CURB INLET @ STA 446+30.01
451+66.74	-	455+50.26		384	10	OUTLET INTO CURB INLET @ STA 451+66.73
456+61.26	-	460+50.73		390		OUTLET INTO CURB INLET @ STA 456+61.26
460+50.73	-	464+16.40		366		OUTLET INTO CURB INLET @ STA 460+50.73
467+22.56			1		22	
467+22.56	-	471+25.99		403		
471+25.99	-	476+00.00		474		OUTLET INTO CULVERT @ STA 471+25.99
476+00.00			1		22	
476+00.00	-	480+37.10		437		
IL 13 EASTBOUND						
443+90.94			1		22	
443+90.94	-	448+06.38		416		
448+06.38	-	451+64.43		358		OUTLET INTO CULVERT @ STA 448+05.97
451+64.57	-	455+50.94		386		OUTLET INTO CULVERT @ STA 451+65.30
456+61.47	-	461+00.00		439		OUTLET INTO CURB INLET @ STA 456+61.36
461+00.00	-	465+04.00		404		OUTLET INTO CURB INLET @ STA 461+00.00
467+95.22			1		22	
467+95.22	-	473+00.00		505		
473+00.00			1		22	
473+00.00	-	478+00.00		500		
478+00.00			1		22	
478+00.00	-	479+50.00		150		
IL 13 MEDIAN						
459+71.48			2		44	
459+71.48	-	465+16.52		546		
459+71.48	-	465+49.61		578		
466+74.92	-	471+34.97		460		
471+34.97			1		22	
467+06.03	-	472+61.62		557		
472+61.62			1		22	
PROJECT TOTALS			11	8,729	262	