

REMOVAL SCHEDULE

LOCATION				TREE REMOVAL			REMARKS
				OFFSET FEET	(6 TO 15 UNITS DIAMETER) UNIT	(OVER 15 UNITS DIAMETER) UNIT	
STATION	TO	STATION					
IL 13 WESTBOUND							
441+20	LT		62	8			
441+35	LT		62		17		
441+50	LT		63	10			
441+99	LT		66	8			
442+12	LT		68	8			
442+17	LT		43	11			
442+37	LT		37	12			
442+38	LT		36	10			
442+43	LT		49		48		
442+91	LT		51		33		
465+66	LT		50	13			
477+56	LT		76		17		
447+85	LT		76		25		
478+86	LT		71		24		
479+31	LT		75		28		
479+71	LT		78		22		
IL 13 EASTBOUND							
446+33	RT		121	12			
446+90	RT		120	10			
447+02	RT		124	7			
447+70	RT		121	10			
447+72	RT		123	9			
448+02	RT		134	7			
448+36	RT		121	10			
448+78	RT		124	15			
448+90	RT		121		16		
449+10	RT		115		24		
449+16	RT		119	11			
451+26	RT		120	8			
451+68	RT		135	6			
451+99	RT		111	11			
452+19	RT		115		24		
452+41	RT		119	13			
452+54	RT		118	13			
452+77	RT		118	12			
PLAZA DRIVE WEST							
10+23	LT		32		25		
CITY STREET NORTHWEST							
0+72	LT		35	7			
0+72	LT		35	8			
0+86	LT		35	12			
1+11	LT		34	13			
1+31	LT		34	10			
1+31	LT		34		26		
1+43	LT		34	12			
1+53	LT		37	6			
1+53	LT		37	15			
1+56	LT		16	13			
1+56	LT		16	9			
1+60	LT		38	7			
1+61	LT		26	6			
SUBTOTALS				352	329		

LOCATION				TREE REMOVAL			REMARKS
				OFFSET FEET	(6 TO 15 UNITS DIAMETER) UNIT	(OVER 15 UNITS DIAMETER) UNIT	
STATION	TO	STATION					
CITY STREET NORTHWEST CONTINUED							
1+61	LT		26	13			
1+61	LT		26	12			
1+61	LT		26	9			
1+62	RT		6		30		
1+67	LT		35		23		
1+78	LT		33	11			
2+41	RT		30		20		
2+78	RT		29		19		
3+25	RT		29		17		
3+25	RT		29	13			
3+25	RT		29	10			
3+54	LT		29	10			
CITY STREET NORTH							
0+47	RT		51	6			
0+47	RT		51	6			
0+54	RT		48	8			
0+54	RT		48	8			
0+60	RT		43		19		
0+63	RT		53	14			
0+68	RT		52		16		
0+72	RT		62		19		
0+79	RT		40	12			
0+81	RT		42	15			
1+09	RT		45		25		
1+21	RT		43	15			
1+39	RT		31	11			
1+40	RT		35		19		
1+43	RT		35		21		
1+76	RT		35	15			
1+80	RT		42	9			
1+92	RT		44	14			
2+21	RT		38	12			
CITY STREET SOUTHWEST							
1+21	LT		34	11			
1+24	LT		16	12			
1+26	LT		14		20		
1+30	LT		18	9			
1+34	LT		28	12			
1+34	LT		28	10			
1+45	LT		36	12			
1+45	LT		36	12			
1+45	LT		36	13			
1+49	LT		12	12			
1+49	LT		12	11			
1+49	LT		12	11			
1+58	LT		21	10			
1+62	LT		15		17		
1+72	LT		12	11			
1+72	LT		31	14			
1+72	LT		31	14			
1+89	LT		8	11			
1+95	LT		18	6			
SUBTOTALS				414	265		
SHEET TOTALS				766	594		

NOTES:

- IL 13 EASTBOUND LANE CALLOUTS USE IL 13 WESTBOUND LANE ALIGNMENT FOR STATION/OFFSET.