

SN 033-7023 (E), 033-7035 (P) 80% FED 20% ST - HAMILTON COUNTY CONSTRUCTION TYPE CODE - 0040			
CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	140
20700220	POROUS GRANULAR EMBANKMENT	CU YD	158
*25000200	SEEDING, CLASS 2	ACRE	0.25
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23
*25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	23
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23
*25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.5
25100630	EROSION CONTROL BLANKET	SO YD	64
28100107	STONE RIPRAP, CLASS A4	SO YD	57
28200200	FILTER FABRIC	SO YD	57
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	60
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N90	TON	8
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9
44000100	PAVEMENT REMOVAL	SO YD	99

SN 033-7023 (E), 033-7035 (P) 80% FED 20% ST - HAMILTON COUNTY CONSTRUCTION TYPE CODE - 0040			
CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY
48101600	AGGREGATE SHOULDERS, TYPE B	SO YD	21
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	740
54003000	CONCRETE BOX CULVERTS	CU YD	17.1
54011005	PRECAST CONCRETE BOX CULVERTS 10' X 5'	FOOT	42
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	78
78300100	PAVEMENT MARKING REMOVAL	SO FT	26

\*SPECIALTY ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
ci:\pwwork\purdost\adamson\0310200\shl	c:\_seq_index.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000 / 1"	CHECKED -	REVISED -
	PLOT DATE = 5/7/2013	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
776	124B-1	HAMILTON	10	3
CONTRACT NO. 78310				
ILLINOIS FED. AID PROJECT				