

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) RS-9	WILL	15	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO.: 60A58

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	53	53					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	20	20				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	150	150				
40600300	AGGREGATE (PRIME COAT)	TON	47	47					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	135	135				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1305	1305													
40600895	CONSTRUCTING TEST STRIP	EACH	1	1													
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	311	311													
40600990	TEMPORARY RAMP	SQ YD	311	311													
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	74	74													
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1958	1958													
42001300	PROTECTIVE COAT	SQ YD	12	12													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	60	60													
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	218	218													
44201705	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	132	132													
44201709	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	42	42													
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	22	22													
48101200	AGGREGATE SHOULDERS, TYPE B	TON	221	221													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3													
67100100	MOBILIZATION	L SUM	1	1													
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1													
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1809	1809													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19313	19313													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	20	20													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6679	6679													
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19313	19313													

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.I. RTE. 55/I-55 W. FRONTAGE RD.
US 6 (E. EAMES ST.) TO BLUFF RD.

PLOT DATE: 6/18/2007

6/18/2007