

SUMMARY OF QUANTITIES

60B01

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	1000-2A			J000-2A		X2M-2A		Y007		Y030-1E		Y031-1F						Y031-3D			Y032-1F					
				SAUNDERS RD / FIELD DR ROADWAY			ROADWAY		IL RTE 60 BRIDGE		RETAINING WALL		LIGHTING		TRAFFIC SIGNALS						EMERGENCY VEHICLE PREEMPTION			TRAFFIC SURVEILLANCE					
				CP0A (FIELD DR.)	OPUS (SAUNDERS RD)	EDP	IL RTE 60 / I-94 RAMP		IL RTE 60 & I-94 RAMP/UNDERPASS				RIVERWOODS RD/BLVD		SAUNDERS RD / FIELD DR			I-94 RAMP / INTERCONNECT		RIVERWOODS RD/BLVD / I-94 SB RAMP	SAUNDERS RD / I-94 NB RAMP								
				100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% METTAWA	100% LAKE COUNTY	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	100% LAKE COUNTY						
* 84200800	POLE FOUNDATION, REMOVED	EACH	15									0.5	14.5																
* 84400115	RELOCATE EXISTING LIGHTING UNIT	EACH	1									0.5	0.5																
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1										1																
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1										1																
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1										1																
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1															0.45	0.45	0.10									
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET (SPECIAL)	EACH	2																		1	1							
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	3															0.45	0.45	0.10	1	1							
* 86710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125 MM12F SM 12 F	FOOT	11415																		5269	5269						877	
* 87301205	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 1C	FOOT	4819																		2409.5	2409.5							
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2663													290.7	290.7	32.3	32.3						378.5	378.5	807	453	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2881													290.7	290.7	32.3	32.3						371	371	1040	453	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	19064													1626.75	1626.75	180.75	180.75	2665.35	2665.35	592.3	4763	4763					
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2843													537.75	537.75	59.75	59.75				824	824					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	23565													2569.5	2569.5	285.5	285.5	2792.25	2792.25	620.5	5825	5825					
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	169																	14.4	14.4	3.2	68.5	68.5					
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14FT.	EACH	10																				5	5					
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1													0.45	0.45	0.05	0.05										
* 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2																				1	1					
* 87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1																				0.5	0.5					
* 87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1																	0.45	0.45	0.1							
* 87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1																	0.45	0.45	0.1							
* 87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1																				0.5	0.5					
* 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1																				0.5	0.5					
* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	3																	0.45	0.45	0.1	1	1					
* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	3																	0.9	0.9	0.2	0.5	0.5					
* 87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	3													0.45	0.45	0.05	0.05	0.9	0.9	0.2							
* 87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1																	0.45	0.45	0.1							
* 87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1													0.45	0.45	0.05	0.05										
* 87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1													0.45	0.45	0.05	0.05										
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	60													1.8	1.8	0.2	0.2				28	28					
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8																				4	4					
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4																	1.8	1.8	0.4							

* - SPECIALTY ITEM

TYLININTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 9 OF 12

SCALE: NONE
DATE: MAY 8, 2007
DRAWN BY: CBS
CHECKED BY: MPG