

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	119R-2	LAKE	439	15
STA. 432+83.12		TO STA. 470+56.84		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

60B01

SUMMARY OF QUANTITIES

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	1000-2A			J000-2A		X211-2A		Y007		Y030-1E		Y031-1F							Y031-3D			Y032-1F			
				SAUNDERS RD / FIELD DR ROADWAY			ROADWAY		IL RTE 60 BRIDGE	RETAINING WALL	LIGHTING		TRAFFIC SIGNALS				EMERGENCY VEHICLE PREEMPTION											
				CP0A (FIELD DR.)	OPUS (SAUNDERS RD.)	EDP	IL RTE 60 / I-94 RAMP				IL RTE 60 & I-94 RAMP/UNDERPASS	RIVERWOODS RD/BLVD				SAUNDERS RD / FIELD DR		I-94 RAMP/ INTERCONNECT	RIVERWOODS RD/BLVD / I-94 SB RAMP	SAUNDERS RD / I-94 NB RAMP	TRAFFIC SURVEILLANCE							
				100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST		80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST		100% LAKE COUNTY		
* X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	2	2																								
X0321598	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LTD, RESTRICTOR PLATE	EACH	2				1	1																				
* X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	729				60	334.5	334.5																			
* X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	11					5.5	5.5																			
X0322054	REMOVING PRECAST FLARED END SECTIONS	EACH	20					10	10																			
* X0322092	STORM SEWER (WATER MAIN REQUIREMENTS) 48 INCH	FOOT	234					117	117																			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1074					537	537																			
X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	2310					1155	1155																			
* X0322695	MAST ARM, STEEL, STREET LIGHTING, 12 FT.	EACH	2										1	1														
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	3591								1795.5	1795.5																
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	298	4	18	16	130	130																				
* X0323670	PREFORMED DETECTOR LOOP	FOOT	623												86.85	86.85	9.65	9.65	193.5	193.5	43							
* X0323792	LIGHTING CONTROLLER, SINGLE DOOR, CONSOLE TYPE	EACH	2										1	1														
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	24							12	12																	
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	7101	480	1146	610	2432.5	2432.5																				
JS280050	SILT FENCE	FOOT	3828				1914	1914																				
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1776	120	287	153	608	608																				
JS280051	RE-ERECT SILT FENCE	FOOT	957				478.5	478.5																				
JS280020	MANAGEMENT OF EROSION AND SEDIMENT CONTROL	CAL MO	14				7	7																				
JS280040	EROSION AND SEDIMENT CONTROL, CLEANOUT	CU YD	479				239.5	239.5																				
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	2912				1456	1456																				
X0324872	CAST-IN-PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES	SQ FT	103				51.5	51.5																				
X0712400	TEMPORARY PAVEMENT	SQ YD	13547				6773.5	6773.5																				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1				0.5	0.5																				
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	528						264	264																		
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	14				7	7																				
* X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	2																		1	1						
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1																0.45	0.45	0.1							
* X8510200	PAINT TRAFFIC SIGNAL EQUIPMENT	L SUM	1																									
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO.6 1C	FOOT	5081												526.5	526.5	58.5	58.5	677.25	677.25	150.5	962	962					482
* X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	3346																					749.5	749.5	1847		

* - SPECIALTY ITEM

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 11 OF 12

SCALE: NONE
DATE: MAY 8, 2007
DRAWN BY: CBS
CHECKED BY: MPG