

SUMMARY OF QUANTITIES

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	I000-2A			J000-2A		X271-2A		Y007		Y030-1E		Y031-1F						Y031-3D			Y032-1F		
				SAUNDERS RD / FIELD DR ROADWAY			ROADWAY		IL RTE 60 BRIDGE		RETAINING WALL		LIGHTING		TRAFFIC SIGNALS						EMERGENCY VEHICLE PREEMPTION			TRAFFIC SURVEILLANCE		
				CPOA (FIELD DR.)	OPUS (SAUNDERS RD)	EDP	IL RTE 60 / I-94 RAMP						IL RTE 60 & I-94 RAMP / UNDERPASS		RIVERWOODS RD / BLVD			SAUNDERS RD / FIELD DR			I-94 RAMP / INTERCONNECT		RIVERWOODS RD / BLVD / I-94 SB RAMP	SAUNDERS RD / I-94 NB RAMP	TRAFFIC SURVEILLANCE	
				100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% METTAWA	100% LAKE COUNTY	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	100% LAKE FOREST	100% LAKE COUNTY
XX002113	TEMPORARY LIGHTING CONTROLLER	EACH	1										1													
* XX002856	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1																		0.5	0.5				
* XX003418	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4 2/C	FOOT	482																							482
XX003686	REMOVE EXISTING CONCRETE END SECTIONS	EACH	15				7.5	7.5																		
XX005631	UTILITY STRUCTURES TO BE ADJUSTED	EACH	1			1																				
* XX006200	UNINTERRUPTABLE POWER SUPPLY	EACH	4											0.45	0.45	0.05	0.05	0.45	0.45	0.1	1	1				
* XX006767	LIQUIDTIGHT FLEXIBLE METAL CONDUIT, 3/4"	FOOT	20										20													
* XX006768	MAINTAIN LIGHTING SYSTEM	L SUM	1										1													
XX006842	AGGREGATE FOR TEMPORARY ACCESS	TON	4		4																					
* XX011700	WATER MAIN FITTINGS	POUND	40		40																					
XX172700	MANHOLES, TYPE A, 6"-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1				0.5	0.5																		
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	50156	1237	4425	1502	21496	21496																		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1				0.5	0.5																		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6				3	3																		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	11				5.5	5.5																		
△ Z0076600	TRAINEES	HOUR	5000				5000																			

* - SPECIALTY ITEM
 △ - 7080

REVISIONS	
NAME	DATE