

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	119R-2	LAKE	439	28
STA. 432+83.12		TO STA. 470+56.84		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

60B01

PROPOSED PAVEMENT RECONSTRUCTION, WIDENING, AND RESURFACING

LOCATION DESCRIPTION	FROM		TO		PCC PVT 10 JOINTED (SQ YD)	PCC PVT 10 1/4 JOINTED (SQ YD)	HES PCC PVT 10 JT SPL (SQ YD)	GEOTECH FAB F/GR STAB (SQ YD)	AGG SUBGRADE 12 (SQ YD)	STAB SUBBASE HMA 3 (SQ YD)	SUB GRAN MAT B 4 (SQ YD)	PCC BSE CSE 10 1/4 (SQ YD)	LEV BIND MM N70 (TON)	P HMA SC "F" NSO (TON)	PROTECTIVE COAT (SQ YD)	JURISDICTION (ISTHA/IDOT)	
	ALIGNMENT	STATION	ALIGNMENT	STATION													
IL 60 @ RIVERWOODS - NORTH LEG	IL RT 60	433+94.3	IL RT 60	433+98.3				20	20							IDOT	
IL 60 @ RIVERWOODS - SE CORNER	IL RT 60	434+18.3	IL RT 60	434+93.2				145			145	98	6	10		IDOT	
IL 60 @ RIVERWOODS - NE CORNER	IL RT 60	434+22.3	IL RT 60	434+93.2				117			117	59	4	6		IDOT	
IL 60 @ RIVERWOODS	IL RT 60	432+83.1	IL RT 60	434+93.2									227	397		IDOT	
IL 60	IL RT 60	434+59.5	IL RT 60	444+06.4		10902		12205	12205						10902	IDOT	
IL 60	IL RT 60	447+01.6	IL RT 60	458+93.2		13427		15210	15210						13427	IDOT	
IL 60 - WEST OF SAUNDERS (MEDIAN)	IL RT 60	458+93.2	IL RT 60	459+64.7		109		131	131						109	IDOT	
IL 60 - EAST OF SAUNDERS	IL RT 60	460+81.5	IL RT 60	470+56.8		950		1341	1341						950	IDOT	
IL 60 - EAST OF SAUNDERS (MEDIAN)	IL RT 60	460+33.9	IL RT 60	460+88.1		80		80	80						80	IDOT	
IL 60 - EAST OF SAUNDERS (MEDIAN)	IL RT 60	460+80.9	IL RT 60	469+49.8		101		610	610						101	IDOT	
IL 60	IL RT 60	469+91.9	IL RT 60	470+03.8				4	4							IDOT	
IL 60	IL RT 60	470+36.2	IL RT 60	470+46.3				3	3							IDOT	
IL 60	IL RT 60	472+42.2	IL RT 60	472+69.2				11	11							IDOT	
IL 60	IL RT 60	472+45.0	IL RT 60	472+55.1				3	3							IDOT	
I-94 SB EXIT RAMP	SB EX RAMP	114+00.0	SB EX RAMP	118+22.1	1398		672	2954	2954	1398					2070	ISTHA	
I-94 SB ENTRANCE RAMP	SB ENT RAMP	118+66.2	SB ENT RAMP	124+09.7	1764			2903	2903	1764					1764	ISTHA	
I-94 SB ENTRANCE RAMP	SB ENT RAMP	124+09.7	SB ENT RAMP	124+29.7				73	73							ISTHA	
I-94 NB EXIT RAMP	NB EX RAMP	190+12.6	NB EX RAMP	193+72.4				865	865							ISTHA	
I-94 NB EXIT RAMP	NB EX RAMP	193+72.4	NB EX RAMP	199+73.3	1383			4388	4388	3136					1383	ISTHA	
I-94 NB ENTRANCE RAMP	NB ENT RAMP	200+27.6	NB ENT RAMP	204+30.5	3136			2191	2191	1383					3136	ISTHA	
					IDOT TOTAL			25569		29880	29618	262	157	237	413	25569	
					ISTHA TOTAL	7681			672	13374	13374	7681				8353	
					TOTAL	7681	25569	672	43254	42992	7681	262	157	237	413	33922	

CONCRETE MEDIAN

LOCATION DESCRIPTION	OFFSET DIRECTION	FROM		TO		CONC MEDIAN (SQ FT)	PROTECTIVE COAT (SQ YD)	
		ALIGNMENT	STATION	ALIGNMENT	STATION			
IL RT 60	RT	IL RT 60	434+59.5	IL RT 60	434+68.3	55	6	
IL RT 60	LT	IL RT 60	440+93.9	IL RT 60	441+06.4	59	7	
IL RT 60	LT	IL RT 60	441+04.9	IL RT 60	441+12.3	66	7	
IL RT 60	RT	IL RT 60	449+94.3	IL RT 60	450+06.4	128	14	
						IDOT TOTAL	308	34

CONCRETE MEDIAN BARRIER TRANSITION, TYPE V-F

LOCATION DESCRIPTION	FROM			TO			CONC MED BARR TRANS V-F (FOOT)	PROTECTIVE COAT (SQ YD)	
	ALIGNMENT	STATION	OFFSET	ALIGNMENT	STATION	OFFSET			
I-94 MAINLINE	I-94	3119+22.8	0.1 RT	I-94	3119+45.8	0.2 LT	23.0	27	
I-94 MAINLINE	I-94	3120+96.5	0.5 RT	I-94	3121+19.5	0.7 LT	23.0	27	
							IDOT TOTAL		
							ISTHA TOTAL	46.0	55
							TOTAL	46.0	55

CONCRETE MEDIAN SURFACE, 4"

LOCATION DESCRIPTION	OFFSET DIRECTION	FROM		TO		CONC MEDIAN SURF 4 (SQ FT)	PROTECTIVE COAT (SQ YD)	
		ALIGNMENT	STATION	ALIGNMENT	STATION			
IL RT 60 - WEST OF SB RAMPS	-	IL RT 60	434+68.3	IL RT 60	434+72.8	16	2	
IL RT 60 - EAST OF NB RAMPS	-	IL RT 60	457+44.5	IL RT 60	458+93.2	360	40	
I-94 SB EXIT RAMP	-	SB EX RAMP	117+35.1	SB EX RAMP	117+77.9	731	81	
I-94 SB ENTRANCE RAMP	-	SB ENT RAMP	119+09.0	SB ENT RAMP	119+39.8	386	43	
I-94 NB EXIT RAMP	-	NB EX RAMP	198+97.0	NB EX RAMP	199+23.6	294	33	
I-94 NB ENTRANCE RAMP	-	NB ENT RAMP	200+66.4	NB ENT RAMP	200+97.3	400	44	
						IDOT TOTAL	376	42
						ISTHA TOTAL	1811	201
						TOTAL	2187	243

CONCRETE MEDIAN TYPE SB-6.12

LOCATION DESCRIPTION	OFFSET DIRECTION	FROM		TO		CONC MED TSB6.12 (SQ FT)	PROTECTIVE COAT (SQ YD)	
		ALIGNMENT	STATION	ALIGNMENT	STATION			
RIVERWOODS BLVD MEDIAN	LT	IL RT 60	433+94.3	IL RT 60	433+98.3	110	12	
IL 60 - MEDIAN	-	IL RT 60	441+96.2	IL RT 60	444+06.6	1277	142	
IL 60 - MEDIAN	-	IL RT 60	447+01.6	IL RT 60	449+23.5	1328	148	
IL 60 - MEDIAN	-	IL RT 60	458+93.2	IL RT 60	459+30.8	192	21	
						IDOT TOTAL	2907	323

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS RTE 60 OVER I-94

SCHEDULE OF QUANTITIES
PROPOSED QUANTITIES - SHEET 1 OF 4

SCALE: NONE
DATE: MAY 8, 2007

DRAWN BY: MPG
CHECKED BY: RTM

05/07/2007 11:25:51 AM