

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1374	0406 WRS	COOK	43	5
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

D-91-106-07

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		I000 ROADWAY	Y031-IF SIGNAL					CODE NO	ITEM		UNIT	I000 ROADWAY	Y031-IF SIGNAL			
* 87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1		1				* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH			1				
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1				* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH			1				
* 87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1				* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT			793				
* 87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1		1				* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT			842				
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4				* XX003418	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4, 2/C	FOOT			398				
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	1		1				* XX005723	VIDEO DETECTION SYSTEM COMPLETE INTERSECTION	EACH			1				
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	30		30				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH			23		23		
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		15													
* 87900200	DRILL EXISTING HANDHOLE	EACH	1		1													
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6		6													
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2													
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2		2													
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2		2													
* 88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2		2													
* 88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	2		2													
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8		8													
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	6		6													
* 88600100	DETECTOR LOOP, TYPE I	FOOT	623	66	557													
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	4		4													
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4														
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	793		793													
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1														
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	4	4														
X6040220	FRAMES AND LIDS, TYPE 1, OPEN LID (CITY OF CHICAGO)	EACH	2	2														

* SPECIALTY ITEM

~~** NON-PARTICIPATING ITEM~~

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
BELMONT AVENUE

4/19/2007