

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2003-071 RS	COOK	91	4

STA.	TO STA.
FED. ROAD DIST. NO. 1 ILLINOIS	FED. AID PROJECT

SUMMARY OF QUANTITIES

URBAN
90/FED./STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	NB ROADWAY 1000	SB ROADWAY 1000	DRAINAGE 1000	BRIDGES X031-2A
20800150	TRENCH BACKFILL	CU YD	134			134	
21400100	GRADING AND SHAPING DITCHES	FOOT	150	150			
35102400	AGGREGATE BASE COURSE, TYPE B, 12"	SO YD	134			134	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	420	207	213		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGE WAYS	TON	98	49	49		
40600895	CONSTRUCTING TEST STRIP	EACH	4	2	2		
40600982	HOT-MIX SURFACE REMOVAL - BUTT JOINT	SO YD	2340	1170	1170		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	1600	834	834		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	24,999	12151	12848		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	19,276	8877	9399		
44000100	PAVEMENT REMOVAL	SO YD	134			134	
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SO YD	349	104	245		
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SO YD	68		68		
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SO YD	1234	907	327		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	730	392	338		
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	380	254	126		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	2169	1844	325		
44201296	DEFORMED BARS - EXPANSION JOINT	EACH	236	236			
44213000	PATCHING REINFORCEMENT	SO YD	3656	2660	996		
44213200	SAW CUTS	FOOT	11076	6726	3990	360	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,705	851	854		
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SO YD	134			134	
50102400	CONCRETE REMOVAL	CU YD	25.7				25.7
50157300	PROTECTIVE SHIELD	SO YD	873				873
50300255	CONCRETE SUPERSTRUCTURE	CU YD	29.8				29.8
50300260	BRIDGE DECK GROOVING	SO YD	791				791
50300300	PROTECTIVE COAT	SO YD	83				83
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4,330				4,330
50800515	BAR SPLICERS	EACH	52				52
52000110	PREFORMED JOINT STRIP SEAL	FOOT	240				240
55021600	RCCP CL III, TYP 2, REIN. CONC. CULVERT, ST. DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	130			130	
59000200	EPOXY CRACK INJECTION	FOOT	200				200

PLOT DATE = 5/23/2007
FILE NAME = 011111
USER NAME = 001001

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.I. 94 (I-94)

SCALE: DATE MAY 2007 DRAWN BY DCS CHECKED BY

Rev. 7-20-07