

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7				
40600300	AGGREGATE (PRIME COAT)	TON	35	35				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	6				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	250	250				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	75	75				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1686	1686				
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	75	75				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	17200	17200				
44000600	SIDEWALK REMOVAL	SQ FT	75	75				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2000	2000				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	520	520				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	258	258				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	155	155				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	103	103				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	3	3				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	36	36				
60404950	FRAMES AND GRATES, TYPE 24	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1910	1910				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000 100% STATE				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7000	7000				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1305	1305				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	180	180				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	200	200				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	635	635				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7000	7000				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1305	1305				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	180	180				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	240	240				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	826	826				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	723	723				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

5/24/2007 10:21:41 AM C:\P2102400.M32