

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	(125BR-2)D	HENRY	34	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	X081-2A 80% FED/ 20% STATE TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	235
20400800	FURNISHED EXCAVATION	CU YD	190
25100630	EROSION CONTROL BLANKET	SQ YD	500
28000300	TEMPORARY DITCH CHECKS	EACH	2
28000400	PERIMETER EROSION BARRIER	FOOT	300
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	25
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	22
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	115
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	146
40600990	TEMPORARY RAMP	SQ YD	80
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	342
42001300	PROTECTIVE COAT	SQ YD	299
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	137
44000700	APPROACH SLAB REMOVAL	SQ YD	137
48203020	HOT-MIX ASPHALT SHOULDERS, 5-3/4"	SQ YD	1,178
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	4.5
50300225	CONCRETE STRUCTURES	CU YD	5.8
50300260	BRIDGE DECK GROOVING	SQ YD	273
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	359
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SQ FT	2618
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4720
50800515	BAR SPLICERS	EACH	92
* 50901050	STEEL RAILING, TYPE SM	FOOT	259
51500100	NAME PLATES	EACH	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	33
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	525
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
*SPECIALTY ITEMS			

CODE NUMBER	ITEM	UNIT	X081-2A 80% FED/ 20% STATE TOTAL QUANTITY
* 63100167	TRAFFIC BARRIER TERMINAL TYPE I, SPECIAL (TANGENT)	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	650
63500105	DELINEATORS	EACH	4
61000400 61000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	5
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	2
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2243
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	681
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	400
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4500
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	16
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	382
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SQ FT	359
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	7
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	291
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	11
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON - REDIRECTIVE), TEST LEVEL 3	EACH	2
*SPECIALTY ITEMS			

PLOT DATE = Wed May 16 11:53:24 2007
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = cshanebcr