

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
638	(129BR-1)D	Henry	8	2
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

Summary of Quantities

100% STATE
SFTY-2A

50102400	CONCRETE REMOVAL	CU YD	4.4
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	310
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	527
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,790
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	48
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	55
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	735
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	24
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	311
70400100	TEMPORARY CONCRETE BARRIER	FOOT	350
78300500	PAINT PAVEMENT MARKING REMOVAL	SQ FT	100
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	538
X0321781	MECHANICAL SPLICE	EACH	180
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	92
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

Summary of Quantities
 FAP Route 638 (IL 82)
 Section (129BR-1)D
 Henry County
 Illinois Route 82 over the Green River
 Structure No. 037-0071

△ REVISED 7/19/07

PLOT DATE = Wed Jul 29 13:44:11 2007
 FILE NAME = D:\S-V-CADD\plans\Henry\037\0071.dgn
 PLOT SCALE = 50.00000 "/ IN.
 USER NAME = ltrk4j