

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
180	(06-2B-1)	BUREAU	14	6

DRAINAGE SCHEDULE

LOCATION	PIPE CULVERT REMOVAL	REMOVE INLET BOX	PIPE CULVERTS, TYPE 1 RCCP 12"	PRECAST REINFORCED CONCRETE FLARED END SECTION	FLUSH INLET BOX FOR MEDIAN STANDARD 542546
	FOOT	EACH	FOOT	EACH	EACH
NORTH ABUTMENT					
SOUTH ABUTMENT	100	1	48	1	1
TOTAL	100	1	48	1	1

SLOPEWALL SCHEDULE

LOCATION	SLOPE WALL REMOVAL	SLOPE WALL 4"	STONE RIPRAP, CLASS A4	STONE DUMPED RIPRAP CLASS, A4	FILTER FABRIC	CONTROLLED LOW-STRENGTH MATERIAL
	SQ YD	SQ YD	SQ YD	TON	SQ YD	CU YD
NORTH ABUTMENT	29	29				33
SOUTH ABUTMENT	584		584	23	584	300
TOTAL	613	29	584	23	584	333

FENCE SCHEDULE

LOCATION	WOVEN WIRE FENCE REMOVAL	WOVEN WIRE FENCE 4'
	FOOT	FOOT
NORTH ABUTMENT	90	90
SOUTH ABUTMENT	90	90
TOTAL	180	180

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULES**  
**FAI ROUTE 180 SECTION (06-2B-1)**  
**BUREAU COUNTY**  
**STA. 521+42**  
**S.N. 006-0052 NB**

Date: April 5, 2007  
c:/projects/main/cm312/details.dgn