

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(46-1)RS-7	PEORIA	62	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

HMA RESURFACING SCHEDULE

LOCATION	AVE. WIDTH	LENGTH	HMA SURF REM - BUTT JT	HMA SURF REM 1-3/4"	TEMPORARY RAMPS	BIT MAT (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURF CSE, MIX E, N70
			SQ YD	SQ YD	SQ YD	TON	TON	TON
EAST INDUSTRIAL	40	5			22.2			
SOUTH ADAMS	59	5			30.6			
ARGENTINA	35	5			19.4			
ROSARIA	50	5			27.8			
WEST PERU	50	5			22.2			
EAST PERU	VAR.	84.3	113.2	356.6	18.9	0.19	0.9	46.0
WEST COLLIER	60	5			22.2			
EAST COLLIER	VAR.	48.5	109.2	95.9	17.8	0.08	0.4	20.1
WEST BRAZIL	VAR.	44	92.2	64.9	15.3	0.06	0.3	15.4
EAST BRAZIL	VAR.	88	91.9	275.4	14.2	0.15	0.7	36.0
WEST BOLIVIA	50	5			13.9			
EAST BOLIVIA	VAR.	48.4	91.0	80.2	15.0	0.07	0.3	16.8
WEST McCLURE	VAR.	53.7	85.3	97.2	14.4	0.07	0.4	17.9
EAST McCLURE	VAR.	45	92.8	64.9	15.3	0.06	0.3	15.5
WEST GARFIELD	35	5			19.4			
EAST CENTER	VAR.	45	104.5	63.4	16.7	0.07	0.3	16.5
ADAMS	VAR.	118	172.0	752.3	28.3	0.37	1.8	90.6
WASHINGTON	VAR.	152.6	111.2	863.3	17.5	0.39	1.9	95.5
TOTALS			1063.3	2714.1	351.1	1.51	7.3	370.3

HMA APPLICATION RATE = 112 LB/SQ YD/IN  
 AGGREGATE (PC) RATE = 4 LB/SQ YD  
 BITUMINOUS (PC) RATE = 0.1 GAL/SQ YD

CCC & G REMOVAL & REPLACEMENT	
LOCATION	FT
TY B612	
RT STA 44+08 - 43+92	16.0
TY B624	
LT STA 68+04 - 68+10	6.0
TOTAL	22.0

TRAFFIC CONTROL & PROTECTION	
LOCATION	LUMP SUM
STANDARD 701602	1
STANDARD 701606	1
STANDARD 701606, SP	1
STANDARD 701701	1

PERMANENT SURVEY MARKERS, TYPE I	
LOCATION	EACH
P.O.T. STA 35+10.53	1
P.O.T. STA 40+08.83	1
P.C. STA 43+32.45	1
P.T. STA 52+40.19	1
P.O.T. STA 61+78.83	1
TOTAL	5

CHANGEABLE MESSAGE SIGN	
LOCATION	CAL MO
PROJECT LIMITS	2
TOTAL	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE: HORIZ.

DRAWN BY: CHECKED BY: