

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	(46-1)RS-7	PEORIA	62	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

TEMPORARY & THERMOPLASTIC PAVEMENT MARKING LINE 4''

STATION	LOCATION	DOUBLE SOLID YELLOW	SOLID & SKIP DASH YELLOW
		FT	FT
STA 77+45 - 77+18	MEDIAN	163.5	
STA 76+65 - 75+11	MEDIAN		402.0
STA 75+11 - 73+88	MEDIAN	433.8	
STA 73+88 - 72+38	MEDIAN	300.0	
STA 71+98 - 71+07	MEDIAN	182.0	
STA 71+07 - 65+67	MEDIAN	2160.0	
STA 65+67 - 63+35	MEDIAN	464.0	
STA 63+35 - 61+68	MEDIAN	510.5	
STA 60+88 - 58+38	MEDIAN		640.0
STA 57+75 - 55+10	MEDIAN		670.0
STA 54+44 - 51+79	MEDIAN		670.0
STA 51+16 - 48+79	MEDIAN		594.0
STA 48+20 - 46+13	MEDIAN		534.0
STA 45+55 - 42+90	MEDIAN		670.0
STA 42+30 - 40+07	MEDIAN		566.0
STA 39+59 - 37+78	MEDIAN		462.0
STA 37+78 - 36+48	LT & RT	260.0	
STA 35+48 - 35+10.53	LT & RT	45.3	
STATION EQUATION			
STA 173+98.44 - 181+14	LT & RT	1435.2	
STA 182+21 - 186+28.99	LT & RT	804.7	
E. McCLURE	MEDIAN	32.0	
W. McCLURE	MEDIAN	58.0	
ADAMS ST.	MEDIAN	190.8	
WASHINGTON ST.	MEDIAN	227.6	
SUBTOTALS		7332.8	5208.0
TOTAL		12540.8	

TEMPORARY & THERMOPLASTIC PAVEMENT MARKING - LINE 12''

LOCATION	YELLOW DIAGONAL
	FT
STA 77+30	17.5
STA 70+94 - 65+67	76.6
STA 63+35 - 61+68	28.9
STA 74+01 - 75+11	36.8
TOTAL	159.8

TEMPORARY & THERMOPLASTIC PAVEMENT MARKING - LINE 24''

LOCATION	WHITE STOP BARS
	FT
NB STA 73+76	24
SB STA 73+60	24
NB STA 42+90	36
SB STA 42+30	36
NB STA 180+85	48
RT TURN LANE	15
SB STA 182+28	38
RT TURN LANE	16
WEST McCLURE	15
EAST McCLURE	16
ADAMS	39
WASHINGTON	19
TOTAL	326

PLOT DATE = 6/7/2007  
 FILE NAME = d:\progs\sva2\bart\plan\shet.dgn  
 USER = j... / JL  
 USER NAME = j...

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. DATE  
HORIZ.

DRAWN BY  
CHECKED BY