

SUMMARY OF QUANTITIES

CONTRACT NO. 70637				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
730		MCLEAN	10	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		
• D5 PATCHING 2008-2				

LOCATION OF WORK:

FAP 730 (US-51)

STA. 250+17.29
TO
STA. 600+00.00

MCLEAN COUNTY
URBAN
100% STATE

CONSTRUCTION TYPE CODE:

J000
TOTAL QUANTITY

CODE NO	ITEM	UNIT	TOTAL QUANTITY
X4420191	CLASS B PATCHES, TYPE II, 11 1/4 INCH	SQ YD	128.0
X4420195	CLASS B PATCHES, TYPE II, 12 1/2 INCH	SQ YD	56.0
X4420196	CLASS B PATCHES, TYPE II, 12 3/4 INCH	SQ YD	8.0
X4420199	CLASS B PATCHES, TYPE II, 13 3/4 INCH	SQ YD	8.0
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	80.0
44213200	SAW CUTS	FOOT	1,710.0
67100100	MOBILIZATION	L SUM	1.0
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1.0
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6.0
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.0
Z0017100	DOWEL BARS	EACH	700.0

PLOT DATE : 8/16/2007
 FILE NAME : a:\projects\70637\70637.dwg
 PLOT SCALE : 42.3529 / IN.
 USER NAME : collierb

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES
SCALE:	VERT. DATE	DRAWN BY CHECKED BY