

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	②	SANGAMON	80	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
① FAP 666 & FAP 67				
② (ISP-Z)RS-4; (107Z)RS-B				

CODED PAYITEM	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE								
				ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS	PARKING	ADJUSTMENTS			
				NINTH ST	JEFFERSON ST	NINTH ST - SEE NOTE 1	NINTH ST - SEE NOTE 2	JEFFERSON ST	JEFFERSON ST			
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE / 10% CITY	50% STATE 50% CITY	100% CITY			
SANGAMON CO. 1000		SANGAMON CO. 1000		SANGAMON CO. Y031-1F		SANGAMON CO. Y031-1F		SANGAMON CO. Y025		SANGAMON CO. Y060		
20800150	TRENCH BACKFILL	CU YD	3	3								
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	15	15								
35100700	AGGREGATE BASE COURSE, TYPE A - 8"	SQ YD	15	15								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	47.1	37.4	8.7				1.0			
40600300	AGGREGATE (PRIME COAT)	TON	72	72								
40600635	LEVELING BINDER (MACHINE METHOD), NTO	TON	3889	3889								
40600980	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4686	3130	1556							
40600990	TEMPORARY RAMP	SO YD	849	849								
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", NTO	TON	7697	5085	1295				218		299	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	380	290	98							
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SO YD	67	67								
42101300	PROTECTIVE COAT	SO YD	211	211								
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8 INCH	SO YD	27	27								
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	1078	983		82		13				
42400800	DETECTABLE WARNINGS	SO FT	140	140								
44000100	PAVEMENT REMOVAL	SQ YD	15	15								
44000198	HOT-MIX SURFACE REMOVAL, VARIABLE DEPTH	SO YD	90,614	69,421	15,031				2604		3558	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	181	181								
44000600	SIDEWALK REMOVAL	SO FT	1154	1041		100		13				
44200164	PAVEMENT PATCHING, TYPE I, 14 INCH	SO YD	24	24								
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	512	411	101							
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	550	506	44							
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	785	601	184							
44213200	SAW CUTS	FOOT	50	50								
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	10	10								
56109210	WATER VALVES TO BE ADJUSTED	EACH	145	83							62	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1								
60255500	MANHOLES TO BE ADJUSTED	EACH	138	70							68	
60260100	INLETS TO BE ADJUSTED	EACH	1	1								
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	105	105								
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	10	10								
* 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1								
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	2							

NOTE 1: NINTH ST WITH INTERSECTIONS OF: MADISON, JEFFERSON, AND SOUTH GRAND
 NOTE 2: NINTH ST WITH INTERSECTIONS OF: CONVERSE, ENOS, CARPENTER, WASHINGTON, AND COOK
 * SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 666 (I-55 BUSINESS LOOP-NINTH STREET)
 FAP 67 (IL 97/IL 29-JEFFERSON STREET)
 SCALE: VERT. DATE
 DRAWN BY CHECKED BY

PLT: BAE
 FILE: BAE
 PLOT SCALE: ESCALES
 USER NAME: BAE

Rev.