

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	②	SANGAMON	80	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
① FAP 666 & FAP 67		② ISP-ZIRS-4; 11072RS-8		

CODED PAY ITEM	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY NINTH ST	ROADWAY JEFFERSON ST	TRAFFIC SIGNALS NINTH ST - SEE NOTE 1	TRAFFIC SIGNALS NINTH ST - SEE NOTE 2	PARKING JEFFERSON ST	ADJUSTMENTS JEFFERSON ST	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE / 10% CITY	50% STATE 50% CITY	100% CITY	
				URBAN SANGAMON CO. 1000	URBAN SANGAMON CO. 1000	URBAN SANGAMON CO. Y031-1F	URBAN SANGAMON CO. Y031-1F	URBAN SANGAMON CO. 7025	URBAN SANGAMON CO. 7000	
67100100	MOBILIZATION	L SUM	1	0.75	0.25					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0	1					
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.75	0.25					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.75	0.25					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.75	0.25					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14	14						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5983	5370	613					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1993	1789	204					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	36			18	18			
* 72000200	SIGN PANEL - TYPE 2	SQ FT	36			36				
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	24230	22747	1483					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	390	390						
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	1711	815	896					
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	4934	4934						
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	16450	10264	4000			2186		
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	1808	984	824					
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	336	336						
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	507	507						
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	47	47						
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	857	750	107					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	857	750	107					
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	6			6				
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	58			51	7			
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	43			43				
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	11			11				
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	94			94				
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	197			197				
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	97			97				
81400100	HANDHOLE	EACH	3			3				
81400300	DOUBLE HANDHOLE	EACH	1			1				

NOTE 1: NINTH ST WITH INTERSECTIONS OF: MADISON, JEFFERSON, AND SOUTH GRAND
 NOTE 2: NINTH ST WITH INTERSECTIONS OF: CONVERSE, ENOS, CARPENTER, WASHINGTON, AND COOK

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 666 (I-55 BUSINESS LOOP-NINTH STREET)
 FAP 67 (IL 97/IL 29-JEFFERSON STREET)
 SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY
 CHECKED BY

PLT DATE : 08/15/05
 PLOT SCALE : 1"=50'
 USER NAME : MUSEB