

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	②	SANGAMON	80	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
① FAP 666 & FAP 67				
② (SP-2)RS-4 & (1072)RS-8				

**PAVEMENT MARKING**

LOCATION	PREFORMED PLASTIC PAVEMENT MARKING TYPE B					POLYUREA PAVEMENT MARKING TYPE I					RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	WORK ZONE PAVEMENT MARKING REMOVAL	SHORT TERM PAVEMENT MARKING	THERMOPLASTIC PAVEMENT MARKING			
	LINE 5" SKIP DASH WHITE	LINE 6" SOLID WHITE	LINE 6" SOLID BLUE	LINE 24" SOLID WHITE	LETTERS AND SYMBOLS WHITE	LINE 5" SKIP DASH WHITE	LINE 5" SOLID YELLOW	LINE 5" SKIP DASH YELLOW	LINE 6" SOLID WHITE	LINE 12" SOLID YELLOW					LINE 5" SKIP DASH WHITE	LINE 5" YELLOW	LINE 12" YELLOW	
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	SQ FT	FOOT	FOOT	FOOT	FOOT	
<b>NINTH STREET</b>																		
STA 54+47.90 TO STA 45+94.43	421	236			88.0						66	66	137	412	241	1965		
<b>NORTH GRAND AVENUE</b>																		
STA 45+01.00 TO STA 36+82.00	405	540		97	61.6						62	62	155	464	61	1942		
STA 36+28.40 TO STA 32+09.80	209	419			17.6						26	26	83	250		823		
STA 31+49.80 TO STA 27+42.12	204	408									22	22	82	245		815		
STA 27+00.06 TO STA 21+48.96	277	549									30	30	110	331		1105		
<b>ENOS STREET</b>																		
STA 20+55.38 TO STA 16+81.91	188	375		53							20	20	75	225		750		
STA 16+31.71 TO STA 12+88.30	167	343			17.6						28	28	83	248		1127	38	
<b>CARPENTER STREET</b>																		
STA 12+01.15 TO STA 9+06.50	138	201		61	26.4						24	24	50	151		552		
STA 8+13.75 TO STA 0+87.50	347	278			52.8						56	56	121	363		1507	55	
STA 0+87.50 TO STA 0+60.29						14	42		27	480			5	15				
<b>MADISON STREET</b>																		
STA 10+80.81 TO STA 11+71.80				112		46	144	90		47			11	33				
STA 11+71.80 TO STA 14+06.79	117				17.6						24	24	31	94	118	470	49	
<b>JEFFERSON STREET</b>																		
STA 14+89.75 TO STA 18+07.25	158	228		57	84.8						24	24	57	172		634		
<b>WASHINGTON STREET</b>																		
STA 19+00.00 TO STA 22+22.84	161	125		113	17.6						26	26	65	194		1042	85	
<b>ADAMS STREET</b>																		
STA 23+09.35 TO STA 26+35.32	163	263		69	35.2						26	26	61	183		655		
<b>MONROE STREET</b>																		
STA 27+22.58 TO STA 30+47.34	163	158		109	17.6						26	26	61	184		867	63	
<b>CAPITOL STREET</b>																		
STA 0+31.00 TO STA 12+38.19	567	394			88.0						84	84	177	532	229	2265		
<b>COOK STREET</b>																		
STA 13+37.82 TO STA 16+26.07	147	340		130	44.0						28	28	61	182		555		
<b>LAWRENCE STREET</b>																		
STA 17+16.84 TO STA 40+15.58	1102	751		43	211.2						178	178	364	1092	601	4423	100	
<b>SOUTH GRAND AVENUE</b>																		
		183																
SUBTOTAL	4934	10264		984	815.2	60	186	90	507	47	750	750	1789	5370	1250	21497	390	
					815													
<b>JEFFERSON STREET</b>																		
STA 0+50.50 TO STA 0+64.99													3	8	7			
<b>1ST STREET</b>																		
STA 1+47.63 TO STA 4+93.38		377		72									1	4		14		
<b>2ND STREET</b>																		
STA 5+76.68 TO STA 9+38.94		164	100		76.4						10	10	23	69	172			
STA 9+47.29 TO STA 12+27.80		371		48														
<b>4TH STREET</b>																		
STA 12+95.35 TO STA 16+14.13		458			71.8						10	10	24	72	181			
<b>5TH STREET</b>																		
STA 16+97.73 TO STA 20+15.65		378		144	203.1						8	8	19	56	121			
<b>6TH STREET</b>																		
STA 20+99.04 TO STA 24+17.76		193	100		55.4						10	10	21	64	159			
<b>7TH STREET</b>																		
STA 25+01.17 TO STA 32+18.89		400		48							19	19	21	64	158			
<b>9TH STREET</b>																		
STA 33+04.68 TO STA 40+08.59		415		48							10	10	21	64	159			
<b>11TH STREET</b>																		
		419		96							20	20	48	143	346			
		599	100	161	132.8						20	20	48	143	346			
		460		48							20	20	23	69	166			
		931		111	183.6													
		258																
SUBTOTAL		5886	300	824	895.7						107	107	204	613	1469	14		
					896													
PROJECT TOTAL	4934	16150	300	1808	1710.9	60	186	90	507	47	857	857	1993	5983	2719	21511	390	
					1711													

PLOT DATE = 2/15/2007  
 FILE NAME = I:\projects\72847\72847.dwg  
 PLOT SCALE = 1/8" = 1'-0"  
 USER NAME = jbaughlin

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES OF QUANTITIES**

FAP 666 (I-55 BUSINESS LOOP-NINTH STREET)  
 FAP 67 (IL 97/IL 29-JEFFERSON STREET)

SCALE: VERT.      DRAWN BY  
 DATE              HORIZ.              CHECKED BY