

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	**	12	4

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* - D-6 MEDIAN PROTECTION 2007-1
 ** - ADAMS, MORGAN, PIKE, SANGAMON AND SCOTT COUNTIES

SCHEDULE FOR SAFETY IMPROVEMENTS

GENERAL LOCATION	DESCRIPTION OF HAZARD	STA OF HAZARD	EXISTING MEDIAN WIDTH	EXISTING SHOULDER WIDTH	HAZARD OFFSET FROM EDGE OF PAVEMENT	WIDTH OF HAZARD	LENGTH OF HAZARD	PROPOSED IMPROVEMENT SEE DETAIL	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL REMOVAL	SPBGR TYPE A	GUARDRAIL REFLECTORS	TRAFFIC BARRIER TERMINAL TYPE 1, SPL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6 SPECIAL
		(MILE STA)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(A, B, OR C)	(FOOT)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)
I-72 PIKE COUNTY																
(6S075I072R002.9)	SIMPLE SPAN SIGN TRUSS (EB MED.)	2.9	54.0	6.0	11.5	2.5	12.0	A	--	--	112.5	4.0	1	1	1	--
(6S075I072R003.7)	SIMPLE SPAN SIGN TRUSS (EB MED.)	3.7	115.0	6.0	40.0	2.5	14.6	A	--	--	62.5	4.0	1	1	1	--
(6S075I072L005.3)	SIMPLE SPAN SIGN TRUSS (WB OUT.)	--	--	--	36.1	--	--	A	--	--	62.5	4.0	1	1	1	--
(6S075I072L005.3)	SIMPLE SPAN SIGN TRUSS (WB MED.)	5.3	53.3	6.0	12.0	2.5	12.0	A	--	--	112.5	4.0	1	1	1	--
I-72 PIKE COUNT									0.0	0.0	350.0	16.0	4.0	4.0	4.0	0.0

SCHEDULE FOR SAFETY IMPROVEMENTS

GENERAL LOCATION	DESCRIPTION OF HAZARD	STA OF HAZARD	EXISTING MEDIAN WIDTH	EXISTING SHOULDER WIDTH	HAZARD OFFSET FROM EDGE OF PAVEMENT	WIDTH OF HAZARD	LENGTH OF HAZARD	PROPOSED IMPROVEMENT SEE DETAIL	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL REMOVAL	SPBGR TYPE A	GUARDRAIL REFLECTORS	TRAFFIC BARRIER TERMINAL TYPE 1, SPL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6 SPECIAL
		(MILE STA)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(A, B, OR C)	(FOOT)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)
I-72 SCOTT COUNTY																
SN 086-0030	MEDIAN BRIDGE PIER (EB)	47.2	108.0	6.0	52.5	3.0	22.0	A	--	--	50.0	4.0	1	1	1	--
SN 086-0030	MEDIAN BRIDGE PIER (WB)	47.2	108.0	6.0	52.5	3.0	22.0	A	--	--	50.0	4.0	1	1	1	--
SN 086-0029	MEDIAN BRIDGE PIER (EB)	49.5	86.5	6.0	42.0	2.5	24.2	A	--	--	62.5	4.0	1	1	1	--
SN 086-0029	MEDIAN BRIDGE PIER (WB)	49.5	86.5	6.0	42.0	2.5	24.2	A	--	--	62.5	4.0	1	1	1	--
SN 086-0027	MEDIAN BRIDGE PIER (EB)	52.0	88.9	6.0	44.0	2.9	63.0	A	--	--	100.0	4.0	1	1	1	--
SN 086-0027	MEDIAN BRIDGE PIER (WB)	52.0	88.9	6.0	44.0	2.9	63.0	A	--	--	100.0	4.0	1	1	1	--
SN 086-0026	MEDIAN BRIDGE PIER (EB)	54.3	87.5	6.0	42.5	2.5	24.0	A	--	--	62.5	4.0	1	1	1	--
SN 086-0026	MEDIAN BRIDGE PIER (WB)	54.3	87.5	6.0	42.5	2.5	24.0	A	--	--	62.5	4.0	1	1	1	--
I-72 SCOTT COUNTY SUB-TOTAL =									0.0	0.0	550.0	32.0	8.0	8.0	8.0	0.0

PLOT DATE = 5/10/2007
 FILE NAME = c:\p\projects\d653007\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAI 72
 SECTION D-6 MEDIAN PROTECTION 2007-1
 ADAMS, MORGAN, PIKE, SANGAMON
 AND SCOTT COUNTIES