

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	**	12	5

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* - D-6 MEDIAN PROTECTION 2007-1
 ** - ADAMS, MORGAN, PIKE, SANGAMON AND SCOTT COUNTIES

SCHEDULE FOR SAFETY IMPROVEMENTS

GENERAL LOCATION	DESCRIPTION OF HAZARD	STA OF HAZARD	EXISTING MEDIAN WIDTH	EXISTING SHOULDER WIDTH	HAZARD OFFSET FROM EDGE OF PAVEMENT	WIDTH OF HAZARD	LENGTH OF HAZARD	PROPOSED IMPROVEMENT SEE DETAIL	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL REMOVAL	SPBGR TYPE A	GUARDRAIL REFLECTORS	TRAFFIC BARRIER TERMINAL TYPE 1, SPL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6 SPECIAL
		(MILE STA)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(A, B, OR C)	(FOOT)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)
I-72 MORGAN COUNTY																
SN 069-0053	MEDIAN BRIDGE PIER (EB)	57.9	88.1	6.0	43.2	2.5	26.0	B	--	--	200.0	4.0	1	1	1	--
SN 069-0053	MEDIAN BRIDGE PIER (WB)	57.9	88.1	6.0	42.4	2.5	26.0	B	--	--	200.0	4.0	1	1	1	--
SN 069-0054	MEDIAN BRIDGE PIER (EB)	59.0	88.5	6.0	43.0	2.5	28.0	B	--	--	200.0	4.0	1	1	1	--
SN 069-0054	MEDIAN BRIDGE PIER (WB)	59.0	88.5	6.0	43.0	2.5	28.0	B	--	--	200.0	4.0	1	1	1	--
(6S0691072R059.7)	SIMPLE SPAN SIGN STRUCTURE (WB)	60.3	87.2	6.0	48.4	2.3	10.8	A	--	--	37.5	4.0	1	1	1	--
(6S0691072R059.7)	SIMPLE SPAN SIGN STRUCTURE (EB)	60.3	87.2	6.0	36.5	2.3	10.8	A	--	--	62.5	4.0	1	1	1	--
(6S0691072L060.9)	SIMPLE SPAN SIGN STRUCTURE (WB)	60.9	87.5	6.0	37.0	2.5	11.0	A	--	--	62.5	4.0	1	1	1	--
(6S0691072L060.9)	SIMPLE SPAN SIGN STRUCTURE (EB)	60.9	87.5	6.0	48.0	2.5	11.0	A	--	--	37.5	4.0	1	1	1	--
SN 069-0034	MEDIAN BRIDGE PIER (EB)	64.2	87.1	6.0	42.2	2.9	62.0	A	--	--	100.0	4.0	1	1	1	--
SN 069-0034	MEDIAN BRIDGE PIER (WB)	64.2	87.1	6.0	42.0	2.9	62.0	A	--	--	100.0	4.0	1	1	1	--
SN 069-0037	MEDIAN BRIDGE PIER (EB)	66.8	86.9	6.0	41.4	2.5	24.0	A	--	--	62.5	4.0	1	1	1	--
SN 069-0037	MEDIAN BRIDGE PIER (WB)	66.8	86.9	6.0	43.0	2.5	24.0	A	--	--	62.5	4.0	1	1	1	--
SN 069-0044	MEDIAN BRIDGE PIER (EB)	68.6	88.1	6.0	42.1	3.4	109.5	A	--	--	150.0	4.0	1	1	1	--
SN 069-0044	MEDIAN BRIDGE PIER (WB)	68.6	88.1	6.0	42.6	3.4	109.5	B	--	--	287.5	4.0	1	1	1	--
SN 069-0045	MEDIAN BRIDGE PIER (EB)	69.1	88.2	6.0	40.7	6.5	28.0	B	--	--	225.0	4.0	1	1	1	--
SN 069-0045	MEDIAN BRIDGE PIER (WB)	69.1	88.2	6.0	41.0	6.5	28.0	B	--	--	225.0	4.0	1	1	1	--
SN 069-0047	MEDIAN BRIDGE PIER (EB)	69.7	87.8	6.0	43.1	2.5	25.0	A	--	--	62.5	4.0	1	1	1	--
SN 069-0047	MEDIAN BRIDGE PIER (WB)	69.7	87.8	6.0	42.2	2.5	25.0	A	--	--	62.5	4.0	1	1	1	--
SN 069-0050	MEDIAN BRIDGE PIER (EB)	71.3	86.7	6.0	42.1	2.5	25.0	B	--	--	200.0	4.0	1	1	1	--
SN 069-0050	MEDIAN BRIDGE PIER (WB)	71.3	86.7	6.0	42.1	2.5	25.0	A	--	--	62.5	4.0	1	1	1	--
SN 069-0051	MEDIAN BRIDGE PIER (EB)	73.8	87.6	6.0	42.7	2.5	25.0	A	--	--	62.5	4.0	1	1	1	--
SN 069-0051	MEDIAN BRIDGE PIER (WB)	73.8	87.6	6.0	42.4	2.5	25.0	A	--	--	62.5	4.0	1	1	1	--
SN 069-0052	MEDIAN BRIDGE PIER (EB)	75.8	87.5	6.0	42.0	2.9	61.0	A	--	--	100.0	4.0	1	1	1	--
SN 069-0052	MEDIAN BRIDGE PIER (WB)	75.8	87.5	6.0	42.6	2.9	61.0	A	--	--	100.0	4.0	1	1	1	--
I-72 MORGAN COUNTY SUB-TOTAL =									0.0	0.0	2925.0	96.0	24.0	24.0	24.0	0.0

PLOT DATE = 5/10/2007
 FILE NAME = c:\p\projects\d653007\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAI 72
 SECTION D-6 MEDIAN PROTECTION 2007-1
 ADAMS, MORGAN, PIKE, SANGAMON
 AND SCOTT COUNTIES