

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	*	**	12	7

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

* - D-6 MEDIAN PROTECTION 2007-1
 ** - ADAMS, MORGAN, PIKE, SANGAMON AND SCOTT COUNTIES

SCHEDULE FOR SAFETY IMPROVEMENTS

GENERAL LOCATION	DESCRIPTION OF HAZARD	STA OF HAZARD	EXISTING MEDIAN WIDTH	EXISTING SHOULDER WIDTH	HAZARD OFFSET FROM EDGE OF PAVEMENT	WIDTH OF HAZARD	LENGTH OF HAZARD	PROPOSED IMPROVEMENT SEE DETAIL	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL REMOVAL	SPBGR TYPE A	GUARDRAIL REFLECTORS	TRAFFIC BARRIER TERMINAL TYPE 1, SPL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6 SPECIAL
		(MILE STA)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(A, B, OR C)	(FOOT)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)
I-72 SANGAMON COUNTY (CONTINUED)																
SN 084-0152	WB MEDIAN SHOULDER	106.8	--	--	--	--	--	C	125.0	1	350.0	4.0	1	1	--	1
SN 084-0154	MEDIAN BRIDGE PIER (EB)	108.1	88.0	6.0	42.2	2.8	60.5	A	--	--	100.0	4.0	1	1	1	--
SN 084-0154	MEDIAN BRIDGE PIER (WB)	108.1	88.0	6.0	43.0	2.8	60.5	A	--	--	100.0	4.0	1	1	1	--
SN 084-0155	MEDIAN BRIDGE PIER (EB)	111.1	89.1	6.0	43.8	2.5	25.5	A	--	--	62.5	4.0	1	1	1	--
SN 084-0155	MEDIAN BRIDGE PIER (WB)	111.1	89.1	6.0	42.8	2.5	25.5	A	--	--	62.5	4.0	1	1	1	--
SN 084-0156	MEDIAN BRIDGE PIER (EB)	114.2	88.5	6.0	42.9	3.0	60.9	A	--	--	100.0	4.0	1	1	1	--
SN 084-0156	MEDIAN BRIDGE PIER (WB)	114.2	88.5	6.0	42.6	3.0	60.9	A	--	--	100.0	4.0	1	1	1	--
SN 084-0158	EB MEDIAN SHOULDER	116.3	--	--	--	--	--	C	125.0	1	400.0	4.0	1	1	--	1
SN 084-0157	WB MEDIAN SHOULDER	116.4	--	--	--	--	--	C	125.0	1	400.0	4.0	1	1	--	1
SN 084-0159	MEDIAN BRIDGE PIER (EB)	117.2	87.6	6.0	42.4	2.5	19.4	A	--	--	62.5	4.0	1	1	1	--
SN 084-0159	MEDIAN BRIDGE PIER (WB)	117.2	87.6	6.0	42.7	2.5	19.4	A	--	--	50.0	4.0	1	1	1	--
SN 084-0160	MEDIAN BRIDGE PIER (EB)	119.3	86.7	6.0	42.1	2.5	19.6	A	--	--	62.5	4.0	1	1	1	--
SN 084-0160	MEDIAN BRIDGE PIER (WB)	119.3	86.7	6.0	42.1	2.5	19.6	A	--	--	62.5	4.0	1	1	1	--
SN 084-0161	MEDIAN BRIDGE PIER (EB)	121.3	87.6	6.0	42.2	2.5	20.4	A	--	--	62.5	4.0	1	1	1	--
SN 084-0161	MEDIAN BRIDGE PIER (WB)	121.3	87.6	6.0	42.9	2.5	20.4	A	--	--	62.5	4.0	1	1	1	--
SN 084-0162	MEDIAN BRIDGE PIER (EB)	122.3	88.0	6.0	42.8	2.8	60.9	A	--	--	100.0	4.0	1	1	1	--
SN 084-0162	MEDIAN BRIDGE PIER (WB)	122.3	88.0	6.0	42.4	2.8	60.9	A	--	--	100.0	4.0	1	1	1	--
I-72 SANGAMON COUNTY SUB-TOTAL =									1450.0	12.0	8637.5	256.0	64.0	64.0	52.0	8.0

SUMMARY

GENERAL LOCATION	GUARDRAIL REMOVAL	TRAFFIC BARRIER TERMINAL REMOVAL	SPBGR TYPE A	GUARDRAIL REFLECTORS	TRAFFIC BARRIER TERMINAL TYPE 1, SPL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED	TRAFFIC BARRIER TERMINAL TYPE 2	TRAFFIC BARRIER TERMINAL TYPE 6 SPECIAL
	(FOOT)	(EACH)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
I-72 PIKE COUNTY SUB-TOTAL =	0.0	0.0	350.0	16.0	4.0	4.0	4.0	0.0
I-72 SCOTT COUNTY SUB-TOTAL =	0.0	0.0	550.0	32.0	8.0	8.0	8.0	0.0
I-72 MORGAN COUNTY SUB-TOTAL =	0.0	0.0	2925.0	96.0	24.0	24.0	24.0	0.0
I-72 SANGAMON COUNTY SUB-TOTAL =	1450.0	12.0	8637.5	256.0	64.0	64.0	52.0	8.0
TOTAL =	1450.0	12.0	12462.5	400.0	100.0	100.0	88.0	8.0

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAI 72
 SECTION D-6 MEDIAN PROTECTION 2007-1
 ADAMS, MORGAN, PIKE, SANGAMON
 AND SCOTT COUNTIES

PLOT DATE = 5/10/2007
 FILE NAME = c:\p\projects\d653007\shsch.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin