

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
793	112BR-2	BOND	52	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE

LOCATION	PAVEMENT MARKING REMOVAL				THERMOPLASTIC PAVEMENT MARKING				POLYUREA PAVEMENT MARKING			TEMPORARY PAVEMENT MARKING LINE - 4"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	REPLACEMENT REFLECTOR 2-WAY AMBER	RAISED REFLECTIVE PAVEMENT MARKER 2-WAY AMBER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) 2-WAY AMBER	
	SOLID CENTERLINE 4" YELLOW	SKIP-DASH CENTERLINE 4" YELLOW	EDGE LINE 4" WHITE		SOLID CENTERLINE 4" YELLOW	SKIP-DASH CENTERLINE 4" YELLOW	EDGE LINE 4" WHITE		SKIP-DASH CENTERLINE 4" YELLOW	EDGE LINE 4" WHITE									
	SQ FT	SQ FT	LT	RT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT								
STATION TO STATION																			
STA 666+47.00 TO STA 669+36.65		23	96.5	96.5		80	289.7	289.7					659	28	229	4	3	1	
STA 669+36.65 TO STA 671+43.36			69.0						50	207	207		464	16	160	2			2
STA 671+43.36 TO STA 674+33.00	49	27	96.5	96.5	146	70	289.8	289.8					796	28	275	4	3	1	
SUB-TOTAL	49	50	262	193	146	150	579.5	579.5	50	207	207								
TOTAL		554				1455				464			1919	72	664	10	6	2	2

RESURFACING SCHEDULE

LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SHOULDERS
STATION TO STATION	TON	TON	TON	SQ YD	TON
STA 668+50.0 TO STA 668+90.0	0.05	0.24	10	106.5	2.3
STA 668+90.0 TO STA 669+36.7	0.05	0.27	18		4.4
STA 671+43.4 TO STA 671+85.0	0.05	0.25	16		4.0
STA 671+85.0 TO STA 672+25.0	0.05	0.24	10	106.5	2.3
TOTAL	0.2	1	54	213	13

TEMPORARY RAMP SCHEDULE

LOCATION	WIDTH FOOT	LENGTH FOOT	TEMPORARY RAMP SQ YD
STA 669+36.65	32	10	36
STA 671+43.36	32	10	36
TOTAL			72

ROW MARKERS SCHEDULE

LOCATION	FURNISHING & ERECTING RIGHT-OF-WAY MARKERS		
STATION	OFFSET	SIDE	EACH
STA 665+75.07	49.29	LT	1
STA 667+50.04	50.76	RT	1
STA 668+00.08	84.23	LT	1
STA 668+50.04	60.79	RT	1
STA 669+25.78	84.19	LT	1
STA 670+77.74	118.05	LT	1
STA 671+65.07	59.12	LT	1
STA 673+50.04	60.94	RT	1
STA 673+50.07	59.09	LT	1
STA 674+50.04	40.97	RT	1
STA 674+50.07	39.03	LT	1
TOTAL			11

STAGING SCHEDULE

LOCATION	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/4"	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANG)	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY RUMBLE STRIP	TEMPORARY PAVEMENT MARKING LINE - 6"	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE)	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE)
	SQ YD	FOOT	FOOT	FOOT	EACH	FOOT	EACH	EACH
STAGE I	262	2	390		6	390	2	
STAGE II			20	390		410		2
TOTAL	262	2 *	410	390	6	800	2	2

\* NOT A TOTAL QUANTITY - SEE GUARDRAIL SCHEDULE.

GUARDRAIL SCHEDULE

LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 1, SPC (TANGENT)	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	TRAFFIC BARRIER TERMINAL, TYPE 6A	TRAFFIC BARRIER TERMINAL, TYPE 2	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
EASTBOUND							5	3	
WESTBOUND							8	3	
NW QUADRANT	140	62.5		1	1				1
NE QUADRANT	190	75	1	1	1	1			2
SW QUADRANT	100	12.5	1		1				1
SE QUADRANT	150	62.5	1		1				1
TOTAL	580	212.5	3 *	2	4	1	13	6	5

\* NOT A TOTAL QUANTITY - SEE STAGING SCHEDULE.

DATE = 08/15/03  
SCALE = AS SHOWN  
REFERENCE = 08/15/03

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 793  
SECTION 112BR-2  
BOND COUNTY  
SN 003-0035