CONTRACT NO. 78005

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	WILLIAMSON	41	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1X-1)N-1,TS-2(13,13X)N-1,TS-1

PAVEMENT AND REMOVAL SCHEDULE

LOCATION STATION TO STATION	PORTLAND CEMENT CONCRETE PAVEMENT, 10" (JOINTED)	SUB BASE GRANULAR MATERIAL, TYPE A, 6"	PROTECTIVE COAT	PAVEMENT REMOVAL
	SQYD	SQYD	SQYD	SQYD
INTERSECTION				
STA 0+54(IL13 EAST) TO STA 886+98.29(IL13 WEST)-STAGE 1	246	246	246	246
STA 0+54(IL13 EAST) TO STA 0+03 (IL13 EAST)-STAGE 2	178	178	178	178
STA 886+50.79(IL13 WEST) TO STA 0+03(IL13 EAST)-STAGE 3	227	227	227	227
STA 0+10.78(IL37 SOUTH) TO STA 0+43.78(IL37 SOUTH)-STAGE 4	172	172	172	172
IL 37 SOUTH LEG				
STA 0+43.78 TO STA 5+49 (NORTHBOUND-STAGE 1)	1963	1963	1963	1963
STA 0+43.78 TO STA 5+49 (SOUTHBOUND-STAGE 4)	1568	1568	1568	1568
IL 37 NORTH LEG				
STA 896+59 TO STA 899+97.48 (NORTHBOUND-STAGE 2)	1080	1080	1080	1080
STA 896+59 TO STA 899+97.48 (SOUTHBOUND-STAGE 3)	1412	1412	1412	1412
IL 13 WEST LEG				
EASTBOUND				
STA 883+25 TO STA 886+50.79 (RT TURN LANE AND THRU LANE-STAGE 5)	1412	1412	1412	1412
STA 883+25 TO STA 886+50.79 (LT TURN LANE AND THRU LANE-STAGE 6)	929	929	929	929
WESTBOUND				
STA 883+25 TO STA 886+50.79 (THRU LANE-STAGE 7)	463	463	463	463
STA 883+25 TO STA 886+50.79 (THRU LANE-STAGE 8)	426	426	426	426
IL 13 EAST LEG				
EASTBOUND				
STA 0+54 TO STA 5+32 (THRU LANE-STAGE 9)	640	640	640	640
STA 0+54 TO STA 5+32 (THRU LANE-STAGE 10)	637	637	637	637
WESTBOUND				
STA 0+54 TO STA 5+32 (LT LANE AND THRU LANE-STAGE 11)	1198	1198	1198	1198
STA 0+54 TO STA 5+32 (THRU LANE-STAGE 12)	645	645	645	645
TOTALS	13,196	13,196	13,196	13,196

PLOT DATE = 5/2/2007
FILE NAME = c:\projects\d98087\sheets.dgn
PLOT SCALE = 50.00 ' / IN.
USER NAME = rodewaldmd