









F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	WILLIAMSON	41	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 01X-1DN-1,TS-2(13,13)XN-1,TS-1

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	POLYUREA PAVEMENT MARKING TYPE 1					LETTERS AND SYMBOLS SQ FT
	4 INCH			12 INCH	24 INCH	
	WHITE FOOT	YELLOW FOOT	DOUBLE YELLOW FOOT	WHITE FOOT	WHITE FOOT	
IL 13 WEST LEG						
STA 883+25 TO STA 886+65 RT 21.6' (SKIPDASH)	85				12	
STA 883+97 TO STA 886+65 RT 33.3' (RT TURN LANE)	268					
STA 883+97 TO 886+51 LT 5.7' (AROUND RAISED MEDIAN)		521				
STA 883+97 TO STA 886+65 RT 9.2' (LT TURN LANE)	268					
STA 883+25 TO STA 886+51 LT 21.7' (SKIPDASH)	82					
STA 886+52 RT 3.2' (STOP BAR)					18	
STA 886+56 RT 87.6' (STOP BAR)					24	
STA 886+65 RT 22.9' (STOP BAR)						
STA 884+07 RT 3.1' (ONLY)						20.8
STA 884+07 RT 39.1' (ONLY)						20.8
STA 884+44 RT 4.2' (TURN ARROW)						15.6
STA 884+44 RT 40.0' (TURN ARROW)						15.6
IL 13 EAST LEG						
STA 0+38.5 LT 20.2' (STOP BAR)					24	
STA 0+38.5 TO STA 0+69.5 LT 32.2' (PAINTED ISLAND)	100			33		
STA 0+38.5 TO STA 5+32 LT 20.2' (SKIPDASH)	124					
STA 0+51 LT 51.7' (STOP BAR)					12	
STA 0+54 LT 2.5' (STOP BAR)					12	
STA 0+54 TO STA 2+13 LT 8.6' (LT TURN LANE)	159					
STA 0+54 TO 2+79 RT 6.2' (AROUND RAISED MEDIAN)		462				
STA 0+54 TO STA 5+32 RT 21.7' (SKIPDASH)	120					
STA 1+69 LT 2.2' (ARROW)						15.6
STA 2+03 LT 2.4' (ONLY)						20.8
STA 2+79 TO STA 5+32 LT 4.0' (DOUBLE SOLID)			253			
STA 2+79 TO STA 5+32 RT 4.3' (DOUBLE SOLID)			253			
STA 3+50 RT 11.2' & 23.4' (RXR)				48		122.4
IL 37 NORTH LEG						
STA 896+59 TO STA 899+76 LT 21.2' (SKIPDASH)	80					
STA 896+59 TO STA 899+76 LT 6.7' (AROUND RAISED MEDIAN)		643				
STA 896+59 TO STA 899+91 RT 22.4' (SKIPDASH)	83					
STA 898+23 TO STA 899+91 RT 8.9' (LT TURN LANE)	168					
STA 898+33 RT 2.8' (ONLY)						20.8
STA 898+58 RT 3.3' (TURN ARROW)						15.6
STA 899+61 TO STA 899+91 RT 33.3' (PAINTED ISLAND)	91			30		
STA 899+75 RT 4.4' (STOP BAR)					14	
STA 899+87 RT 59.8' (STOP BAR)					12	
STA 899+91 RT 22.4' (STOP BAR)					22	
IL 37 SOUTH LEG						
STA 0+55.8 LT 14.1' (STOP BAR)					36	
STA 0+55.8 TO STA 0+82.8 LT 32.2' (PAINTED ISLAND)	81			30		
STA 0+55.8 TO STA 3+01 LT 10.0' (LT TURN LANE)	246					
STA 0+55.8 TO STA 4+02 LT 21.3' (SKIP DASH)	87					
STA 0+55.8 TO STA 4+97.8 RT 8.0' (AROUND RAISED MEDIAN)		895				
STA 0+55.8 TO STA 5+00 RT 20.1' (SKIP DASH)	111					
STA 0+58 LT 56.5' (STOP BAR)					12	
STA 2+89 LT 2.7' (ONLY)						20.8
STA 2+55 LT 2.7' (TURN ARROW)						15.6
SUBTOTAL						
	2153	2521	506	93	246	304
TOTAL						
		5686		93	246	304

DETOUR ROUTE SIGN SCHEDULE

SIGN ID NO.	DESCRIPTION	NUMBER REQUIRED EACH	SIGN SIZE	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT
M4-9R	DETOUR	39	24" x 12"	78	
M1-I100		39	24" x 24"	156	
M5-1R		6	21" x 15"	13.1	
M5-1L		1	21" x 15"	6.6	
M6-1		11	21" x 15"	24.1	
M6-2		2	21" x 15"	4.4	
M6-1L		9	21" x 15"	19.7	
M6-3		8	21" x 15"	17.5	
R3-1		2	24" x 24"	8	
R3-2		2	24" x 24"	8	
R5-2	NO TRUCKS	2	24"x24"	8	
R5-2P	NO TRUCKS	30	24"x18"	90	
R11-3A	ROAD CLOSE 1 MI	2	60" x 30"		37.5
W20-2	DETOUR AHEAD	8	48" x 48"		128
W20-3	ROAD CLOSED AHEAD	2	48" x 48"		64
	TRUCKS ONLY	17	24" x 24"	68	
TOTALS				501.4	229.5

PLOT DATE = 5/2/2007
 FILE NAME = c:\prow\jesta\d99\807\pms\ts.dgn
 USER NAME = pms\jesta