

SECTION 8, TOWNSHIP 35, RANGE 14  
SECTION 17, TOWNSHIP 35, RANGE 14

F. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1629	07-00220-00-RS	COOK	20	02
STA.		TO STA.		
FED. ROAD DIST. NO.	BLK/MI	FED. RD PROJECT		

CONTRACT #83934

SUMMARY OF QUANTITIES				1000	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	
	35800200	AGGREGATE BASE REPAIR	TON	100	
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	
	25200110	SODDING, SALT TOLERANT	SQ YD	150	
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4200	
	40600300	AGGREGATE (PRIME COAT)	TON	50	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	840	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1700	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ FT	270	
	42400800	DETECTABLE WARNINGS	SQ FT	65	
	44000161	HOT-MIX ASPHALT SURFACE REMOVAL 3"	SQ YD	19000	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1000	
	44000600	SIDEWALK REMOVAL	SQ FT	270	
	44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	130	
	44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	160	
	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	910	
	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	19000	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	47	
	60255500	MANHOLE TO BE ADJUSTED	EACH	16	
	60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	2	
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1300	
	67100100	MOBILIZATION	L SUM	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	640	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	280	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11270	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1400	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	190	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	140	
*	88600100	DETECTOR LOOP, TYPE 1	FOOT	150	
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1000	
	X7200400	WORK ZONE PUBLIC INFORMATION SIGNS	EACH	2	
	XX003168	WORK ZONE PAVEMENT MARKING REMOVAL, SPECIAL	FOOT	640	
	XX006948	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	530	

\* - INDICATES SPECIALTY ITEMS

**GENERAL NOTES:**

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTOR'S USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITIES INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- THE NOMINAL THICKNESS OF BITUMINOUS MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS SURFACE IS PLACED.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**VOLLMER ROAD  
STREET RESURFACING  
SUMMARY OF QUANTITIES  
AND GENERAL NOTES**

SCALE: VERT. NA      DRAWN BY RG  
 HORIZ. NA      CHECKED BY JMN  
 DATE 02/09/07