



CONSTRUCTION TYPE CODE: 1000

Item #	Items	Unit	Quantity						
20200100	EARTH EXCAVATION	CU YD	2150.00	EARTH EXCAVATION	CY				
20800150	TRENCH BACKFILL	CU YD	77.00	CONTINGENCY FOR UNDERCUT		650.00			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	650.00	EARTH EXCAVATION		1500.00			
21101615	TOP SOIL, FURNISH AND PLACE 4"	SQ YD	3112.00	TOTAL		2150.00			
25000100	SEEDING CLASS 1	ACRE	0.70	TRENCH BACKFILL	CY				
25000400	NITROGEN FERTILIZER NUTRIENT	LB	58.00	STORM SEWER					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	LB	58.00	99+82 LT		3.00			
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	58.00	99+88 LT		3.00			
25100105	MULCH METHOD 1	ACRE	0.70	100+52 RT		3.00			
28000400	PERIMETER EROSION BARRIER	FOOT	600.00	100+60 LT		3.00			
31101200	SUB BASE GRANULAR MATERIAL, TY-B, 4"	SQ YD	1312.00	100+61 LT		3.00			
35102000	AGGREGATE BASE COURSE TY-B, 8"	SQ YD	1888.00	102+75 RT<		10.00			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	465.00	102+75 TO 105+00 RT		52.00			
40600300	AGGREGATE PRIME COAT	TON	5.00	TOTAL		77.00			
40603085	HOT-MIX ASPHALT BASE COURSE, MIX "D", N70	TON	846.00	GEOTECH FABRIC FOR GROUND STABILIZATION	SY				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	521.00	FOR USE WITH UNDERCUT AND BACKFILL		650.00			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	17.00	TOPSOIL FURNISH AND PLACE, 4"	SY				
44000080	HOT-MIX ASPHALT SURFACE REMOVAL (COLD MILLING)	SQ YD	188.00	ALL AREAS WITHIN CONSTRUCTION LIMITS		3112.00			
44000100	PAVEMENT REMOVAL	SQ YD	621.00	SEEDING, CLASS 1A	ACRE				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1221.00	ALL AREAS WITHIN CONSTRUCTION LIMITS		0.70			
48101600	AGGREGATE SHOULDERS, TYPE B, 8"	SQ YD	132.00	FERTILIZER NUTRIENT	LBS				
48203003	HOT-MIX ASPHALT SHOULDERS, MIX "D", N70	SQ YD	587.00	NITROGEN		58.00			
50105220	PIPE CULVERT REMOVAL	FOOT	68.00	PHOSPHORUS		58.00			
54200643	PIPE CULVERTS, T-1, CS/AL CULVERT PIPE, 18"	FOOT	60.00	POTASSIUM		58.00			
54213660	PRECAST REINFORCED CONC. FLARED END SEC 15"	EACH	3.00	TOTAL		174.00			
54213663	PRECAST REINFORCED CONC. FLARED END SEC 18"	EACH	1.00	PAVEMENT REMOVAL	SQ YD				
54213873	STEEL END SECTIONS 18"	EACH	4.00	OLD RIVER ROAD					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	260.00	13+59 TO 14+31		310.5			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	154.00	15+74 TO 16+40		310.5			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	8.00	TOTAL		621.00			
60243000	INLET SPECIAL, TYPE 2	EACH	5.00	COMBINATION CURB AND GUTTER REMOVAL	FOOT				
60258000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	1.00	LATHAM ROAD AND RADIUS		1221.00			
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	3.00	ALL AREAS WITHIN CONSTRUCTION LIMITS		0.70			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	14.00	MULCH METHOD 1	ACRE				
60608600	COMB CONCRETE CURB AND GUTTER TY M-6.06	FOOT	56.00	ALL AREAS WITHIN CONSTRUCTION LIMITS		0.70			
60610400	COMB CONCRETE CURB AND GUTTER TY B-6.24	FOOT	1344.00	PERIMETER EROSION BARRIER	FOOT				
60625800	ISLAND PAVEMENT, (SPECIAL)	SQ YD	8.00	TOTAL		600.00			
67100100	MOBILIZATION	L SUM	1.00	AGGREGATE SHOULDERS, TYPE B, 8"	SQ YD				
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1.00	OLD RIVER ROAD					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4592.00	13+00 TO 14+31		88.00			
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LTR AND SYM	SQ FT	62.40	15+63 TO 16+40		44.00			
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	7463.00	TOTAL		132.00			
* 78000500	THERMOPLASTIC PAVEMENT MARKING-LINE 8"	FOOT	821.00	SUB BASE GRANULAR MATERIAL, TY-B, 4"	SQ YD				
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	132.00	CONTINGENCY FOR UNDERCUT		150.00			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	156.00	LATHAM ROAD STA 92+73.51 TO STA 105+00.00 RT<		1162.00			
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1.00	TOTAL		1312.00			
* 81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	98.00	HOT MAX ASPHALT SHOULDERS	SY				
* 81603000	UNIT DUCT, 2-1C NO.8, 1/C NO.8, GROUND (XPL-TYPE USE) 3/4" DIA POLYETHYLENE	FOOT	552.00	MIXTURE D, N70					
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	335.00	LATHAM ROAD, 92+73.51 TO 98+75.00 RT<		587.00			
* 82102250	LUMINAIRE, SODIUM VAPOR, HM, 250 WATT	EACH	4.00	TOTAL		587.00			
* 82500530	LIGHTING CONTROLLER, TYPE CB-RCS, 100AMF, 240 VOLT	EACH	1.00	PIPE CULVERT REMOVAL	FOOT				
* 82500605	LIGHTING CONTROLLER, PHOTOCELL RELAY	EACH	1.00	94+93.79 LT		33.00			
* 83002600	LIGHT POLE, ALUMINUM, 4CFT. MH., 15FT. DAVIT ARM	EACH	4.00	96+75.62 LT		35.00			
* 83600200	LIGHT POLE FOUNDATION, 24" DIA.	FOOT	24.00	TOTAL		68.00			
* 83800650	BREAKAWAY DEVICE COUPLING, SS SCREEN	EACH	16.00	BITUMINOUS MATERIALS (PRIME COAT)	GAL				
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2.00	TOTAL		465.00			
XX003140	SHORT-TERM PAVEMENT MARKING REMOVAL	FOOT	4592.00	AGGREGATE (PRIME COAT)	TON				
XX005064	CLASS D PATCHES	SQ YD	43.00	TOTAL		5.00			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.00	PIPE CULVERTS, T-1, CS/AL CULVERT PIPE, 18"	FOOT				
				94+93.79 LT		30.00			
				96+75.62 LT		30.00			
				TOTAL		60.00			

* SPECIALTY ITEMS