

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 621	05-00075 05-RS	SANGAMON	72	3

CONTRACT NO. 93439

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	1000
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18
20200100	EARTH EXCAVATION	CU YD	2,075
20300100	CHANNEL EXCAVATION	CU YD	160
* 20400800	FURNISHED EXCAVATION	CU YD	1,085
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	405
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	2.9
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	290
28000300	TEMPORARY DITCH CHECKS	EACH	48
28000400	PERIMETER EROSION BARRIER	FOOT	215
28000500	INLET AND PIPE PROTECTION	EACH	8
* 28101700	RIPRAP, SPECIAL	TON	537
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	215
* 35101400	AGGREGATE BASE COURSE, TYPE B	TON	56
* 35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	607
* 40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	785
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,103
40600300	AGGREGATE (PRIME COAT)	TON	177
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,508
40600990	TEMPORARY RAMP	SQ YD	421
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	11,852
* 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	7,081
* 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	489
44000100	PAVEMENT REMOVAL	SQ YD	394
44004250	PAVED SHOULDER REMOVAL	SQ YD	56
* 48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,297
* 48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	139
* 48203100	HOT-MIX ASPHALT SHOULDERS	TON	50
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	5.4
50105220	PIPE CULVERT REMOVAL	FOOT	386
* 50800105	REINFORCEMENT BARS	POUND	18,370
54001001	BOX CULVERT END SECTIONS, CULVERT NO.1	EACH	2
54001005	BOX CULVERT END SECTIONS, CULVERT NO.5	EACH	2
54001014	BOX CULVERT END SECTIONS, CULVERT NO.14	EACH	2
54002060	EXPANSION BOLTS 3/4 INCH X 12 INCH	EACH	64
54003000	CONCRETE BOX CULVERTS	CU YD	99.9
54020504	PRECAST CONCRETE BOX CULVERTS 5' X 4' (M273)	FOOT	63
54020603	PRECAST CONCRETE BOX CULVERTS 6' X 3' (M273)	FOOT	50
54010604	PRECAST CONCRETE BOX CULVERTS 6' X 4'	FOOT	57
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	8
542A0241	PIPE CULVERTS, CLASS A, TYPE 1 36"	FOOT	16

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	1000
542A0253	PIPE CULVERTS, CLASS A, TYPE 1 48"	FOOT	56
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	184
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	8
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1
* 54215448	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 48"	EACH	1
* 54248515	CONCRETE COLLAR	EACH	12
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	551
* 60225400	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4
* 60225900	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 8 GRATE	EACH	1
60247310	JUNCTION BOX, SPECIAL 24"	EACH	2
60500060	REMOVING INLETS	EACH	1
61140000	STORM SEWERS, (SPECIAL) 8"	FOOT	60
61140200	STORM SEWERS, (SPECIAL) 12"	FOOT	20
61140400	STORM SEWERS, (SPECIAL) 15"	FOOT	100
63200310	GUARDRAIL REMOVAL	FOOT	138
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	33
67100100	MOBILIZATION	L SUM	1
* 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
* 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
* 70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
* 70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9,336
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	69,800
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,042
* X0392300	DITCH CHECK REMOVAL	EACH	1
* X4420132	CLASS D PATCHES (SPECIAL)	SQ YD	363

* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES

FAS 621 (CH 10)
SECTION 05-00075-05-RS
SANGAMON COUNTY

CUMMINS ENGINEERING CORPORATION

JOB #: 2171
FILE: 2171GENNOTES
DATE: 4/30/07