

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8146	06-00029-00-TL	SANGAMON	67	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• HS-8146(003)				

PAVEMENT SCHEDULE

LOCATION	SUB-BASE GRANULAR MATERIAL TYPE B 4"	AGGREGATE BASE COURSE, TYPE B 6"	HOT-MIX ASPHALT BASE COURSE WIDENING, 7"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N50	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE MIX "D", N50	INCIDENTAL HOT-MIX ASPHALT SURFACING	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH
	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	SQ YD	TON	TON	SQ YD	SQ YD
STA. 31+00 TO STA. 31+05							14				
STA. 31+00, LT. TO STA. 31+40, LT.											
STA. 31+00 TO STA. 45+00				289	8	1,240		434			
STA. 31+04, RT. TO STA. 31+58, RT.											
STA. 31+82, 11' RT. TO STA. 45+00, 12' RT.											
STA. 31+84, RT. TO STA. 31+96, RT.											
STA. 31+72.50, RT. (P.E.)		37		13					4		
STA. 31+76, LT. (FRONTAGE ROAD)				9			33	10			
STA. 31+82, RT. TO STA. 196+52, LT.	1,182		895	314							
STA. 31+93, RT. TO STA. 32+20, RT.											
STA. 32+11, LT. TO STA. 32+31, LT.											
STA. 32+20, 14.08' RT. TO STA. 32+83, 50' RT.											
STA. 32+27, LT. TO STA. 201+66, LT.	236										
STA. 32+28, LT. TO STA. 32+55, LT.											
STA. 32+55, 14.08' LT. TO STA. 36+76.36, 25.89' RT.											
STA. 32+95, RT. (DIANE COURT)	86		127	45		60	12	11			
STA. 33+07, 50' RT. TO STA. 37+09.50, 58.28' RT.										52	
STA. 36+00, LT. (P.E.)											
STA. 36+12, RT. (P.E.)		41		16					4		
STA. 36+43, 19' LT. TO STA. 45+00, 12' LT.											
STA. 36+43, LT. TO STA. 200+63, LT.			61	22							
STA. 37+59.51, 52.10' RT. TO STA. 43+90, 20.08' RT.											
STA. 37+64.72, 59.57' LT. TO STA. 43+90, 20.08' LT.											
STA. 40+23.15, 20.08' LT. TO STA. 40+43.44, 32.44' LT.											84
STA. 40+72, LT. (C.E.)											
STA. 41+00.80, 31.79' LT. TO STA. 41+20.64, 20.08' LT.											
STA. 43+90, RT. TO STA. 45+00, RT.											
STA. 44+06, LT. (C.E.)		30		11					4		
STA. 44+24, LT. TO STA. 45+00, LT.											
STA. 44+95 TO STA. 45+00							14				
STA. 196+52 TO STA. 199+50						135					
STA. 196+52 TO STA. 196+57							14				
STA. 196+52 TO STA. 199+82				81	2			116			
STA. 196+52, 12' LT. TO STA. 199+97, 45' LT.											
STA. 196+52.48, 14.10' LT. TO STA. 199+41.82, 26.04' LT.										56	
STA. 197+29, LT. (P.E.)										20	
STA. 198+17, LT. (P.E.)											
STA. 199+48, RT. TO STA. 45+00 RT.	832		637	223							
STA. 199+48, 22' RT. TO STA. 199+95, 59' RT.											
STA. 200+18, 49' LT. TO STA. 200+63, 21' LT.											
STA. 200+18, 6' LT. TO STA. 201+66, 6' LT.											
STA. 200+18, 6' RT. TO STA. 201+66, 6' RT.											
STA. 200+18 TO STA. 201+66				58	2			72			
STA. 200+19, 45' RT. TO STA. 200+88, 22' RT.											
STA. 200+24.49, 59.54' LT. TO STA. 201+66, 22.35' LT.											
STA. 200+50 TO STA. 201+56						65					
STA. 200+60.25, 28.00' RT. TO STA. 201+66, 21.79' RT.											
STA. 200+88, RT. TO STA. 45+00, LT.			454	159							
STA. 200+90.53, 23.45' RT. TO STA. 200+96.88, 35.93' RT.											
STA. 201+20, RT. (C.E.)											73
STA. 201+37, LT. (P.E.)										15	
STA. 201+42.57, 35.99' RT. TO STA. 201+51.42, 22.04' RT.											
STA. 201+61 TO STA. 201+66							23				
STA. 201+66, RT. TO STA. 45+00, LT.	680										
MISC. PATCHES AND TRANSVERSE CRACKS											
	3,016	108	2,174	1,240	12.0	1,500	110	643	12	143	157

PLOT DATE = 4/27/07
 FILE NAME = S:\16162\DRAWINGS\06152SCH.dgn
 PLOT SCALE = 28.0000 / IN.
 MODEL = Default
 OPERATOR = Franky

REVISIONS	
NAME	DATE
IDOT REVIEW	4/11/07

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 VILLAGE OF CHATHAM
 SECTION 06-00029-00-TL
 SANGAMON COUNTY
 WALNUT ST. / PARK AVE. IMPROVEMENTS

SCALE: VERT. _____ DRAWN BY: SUTHEARD
 HORIZ. _____ CHECKED BY: BOTT
 DATE: 2/14/07

GREENE & BRADFORD, INC.
 CONSULTING ENGINEERS
 OF SPRINGFIELD

COMPUTER FILE NO.
 06152SCH
 PROJECT 06152
 4/11/07 - MML