WA058

HANSON

HANSON PROFESSIONAL SERVICES INC.

815 Commerce Drive, Suite 200
Oak Brook, Illinois 60523
Telephone: 630.990.3800
Fax: 630.990.3801

Illinois Professional Design Firm
Registration No. 184-001084

© Copyright Hanson Professional Service Inc. 2007

WAUKEGAN REGIONAL AIRPORT
WAUKEGAN PORT DISTRICT

3580 North McAree Road
Waukegan, Illinois 60087
Telephone: 847.244.0066
Fax: 847.244.3813

WAUKEGAN REGIONAL AIRPORT

REPAIR AND OVERLAY EAST PORTION OF TAXIWAY A

WAUKEGAN, ILLINOIS

SUMMARY OF QUANTITIES

Item			Quantity	
Number	Description	Unit	Bid	Paid
AR125941	Adjust Stake Mounted Light	Each	48.00	
AR125942	Adjust Base Mounted Light	Each	12.00	
AR150510	Engineer's Field Office	Lump Sum	1.00	
AR156510	Silt Fence	Linear Foot	64.00	
AR156520	Inlet Protection	Each	15.00	
AR201620	Bituminous Base Course - Leveling	Ton	2,270.00	
AR201630	Bituminous Base Test Section	Each	1.00	
AR401610	Bituminous Surface Course	Ton	1,730.00	
AR401650	Bituminous Pavement Milling	Square Yard	1,185.00	
AR401660	Saw and Seal Bit. Joint	Linear Foot	1,120.00	
AR401665	Bituminous Pavement Sawing	Linear Foot	1,000.00	
AR401910	Remove & Replace Bit. Pavement	Square Yard	2,375.00	
AR501665	PCC Pavement Sawing	Linear Foot	690.00	
AR501910	Remove & Replace PCC Pavement	Square Yard	835.00	
AR602510	Bituminous Prime Coat	Gallon	736.00	
AR603510	Bituminous Tack Coat	Gallon	4,077.00	
AR605540	Clean & Seal Joints	Linear Foot	13,215.00	
AR605541	Clean & Seal Cracks	Linear Foot	355.00	
AR620520	Pavement Marking - Waterborne	Square Foot	10,800.00	
AR620525	Pavement Marking - Black Border	Square Foot	1,675.00	
AR800901	Bituminous Pressure Relief Joint	Each	1.00	
AR800943	Remove Mixed Pvmt. - Replace w/ Bit.	Square Yard	81.00	
AR800972	Bituminous Sand Mix - 2"	Square Yard	55.00	
AR800973	Crack Control Material	Linear Foot	125.00	
AR901510	Seeding	Acre	2.10	
AR905520	Topsoiling (From Off Site)	Cubic Yard	1,130.00	
AR908510	Mulching	Acre	2.10	

No.	Drawing Issue Description	Date	By

Date

JUNE 8, 2007

Sheet Title

SUMMARY OF QUANTITIES

83106I8012
Project Number

LDH 03/14/07
Layout By Date

LDH 03/14/07
Designed By Date

RMH 06/08/07
Reviewed By Date

LDH | --- | ---
Drawn By

2

Sheet No.

I:\06JOBS\00831\06I8012\DRAWINGS\SHEETS\02-SUMMARY OF QUANTITIES.DWG JUN 08, 2007 12:15PM LDH