

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2012-042-I	COOK	20	9

CONTRACT: 60V31

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 6' PARALLEL	SIDEWALK 8" R&R (SQFT) 6' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	REMARKS
7158 South Hamlin Avenue/7159 South Avers Avenue	40.0	6.7	0.0	0.0	240.0	0.0		20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
7200 South Hamlin Avenue/7201 South Avers Avenue	40.0	6.7	3.4	0.0	0.0	120.0		20.0	Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind These Two Listed Addresses That Share This Alley Return/Apron
5609 South Karlov Avenue		0.0	0.0	0.0	60.0	0.0			Replace 2 Sidewalk Squares
6001 South Karlov Avenue		0.0	0.0	22.5	900.0	180.0			Replace 36 Front and Side Sidewalk Squares and Courtesy Walks
6043 South Karlov Avenue		0.0	0.0	0.0	60.0	0.0			Replace 2 Sidewalk Squares
6412 South Karlov Avenue		0.0	0.0	36.0	180.0	0.0			Replace 6 Sidewalk Square, Courtesy Walk, and Carriage Walk
6754 South Karlov Avenue		0.0	0.0	31.5	0.0	0.0			Replace 7 Courtesy/Carriage Walk Squares
6800 South Karlov Avenue		0.0	0.0	0.0	210.0	0.0			Replace 7 Cracked Sidewalk Squares - 68th Street Side
6813 South Karlov Avenue		0.0	0.0	22.5	180.0	0.0			Replace 6 Sidewalk Squares and Courtesy Walk
6813 South Karlov Avenue		0.0	0.0	0.0	180.0	0.0			Replace 6 Sidewalk Squares and 2 Courtesy Walk Squares
6858 South Karlov Avenue		0.0	0.0	9.0	180.0	0.0			Repair Alley Return/Apron In its Entirety With Concrete and ADA Ramps Behind This Address
6914 South Karlov Avenue		0.0	0.0	0.0	60.0	0.0			Replace 2 Cracked, Broken Sidewalk Squares
6918 South Karlov Avenue		0.0	0.0	0.0	60.0	0.0			Replace 2 Cracked, Broken Sidewalk Squares
6325 to 6327 South Keating Avenue	11.0	1.9	0.9	9.0	180.0	0.0			Replace 6 Sidewalk Squares, 2 Courtesy Walk Squares, and 11 Feet of Curb
6339 South Keating Avenue		0.0	0.0	9.0	180.0	0.0			Replace 6 Sidewalk Squares and 2 Courtesy Walk Squares
6428 South Keating Avenue		0.0	0.0	0.0	60.0	0.0			Replace 2 Cracked Sidewalk Squares
6558 South Keating Avenue	100.0	16.7	13.4	30.0	0.0	0.0			Replace 100 Feet of Broken, Cracked, and Low Curb and Gutter on the 66th Street of This Address - North Side of Street
6600 South Keating Avenue	100.0	16.7	13.4	30.0	0.0	0.0			Replace 100 Feet of Missing Curb and Gutter on the 66th Street of This Address - South Side of Street
7834 South Keating Avenue	20.0	3.4	1.7	0.0	0.0	120.0	9.0		Replace 4 Broken Sidewalk Squares and Driveway Apron
5559 South Kedvale Avenue		0.0	0.0	0.0	60.0	0.0			Replace 2 Missing Sidewalk Squares on 56th Street Side
5800 South Keeler Avenue		0.0	0.0	22.5	900.0	180.0			Replace 36 Front and Side Sidewalk Squares and Courtesy Walks
5939 South Keeler Avenue		0.0	0.0	9.0	270.0	0.0			Replace 6 to 9 Sidewalk Squares and 2 Courtesy Walk Squares
SUB-TOTAL	311.0	52.1	32.8	231.0	3960.0	600.0	9.0	40.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES