


FILE NAME = S:\JOL\6708-6799\6794\012\Micros\CID00 Sheets\0163722-sh-900.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONST. CODE	CONST. CODE
				80% FED	100% OAK PARK
				20% OAK PARK	SAFETY
				SAFETY	SAFETY
				0031	0031
				URBAN	URBAN
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1	
81100510	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., PVC COATED GALVANIZED STEEL	FOOT	1,097	1,097	
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	38	38	
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	13	13	
81702420	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 8	FOOT	677	677	
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	20	20	
87301405	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 16 1 PAIR	FOOT	320	320	
D2003776	EVERGREEN, THUJA OCCIDENTALIS SMARAGD (EMERALD GREEN AMERICAN ARBORVITAE), 5' HEIGHT, BALLED AND BURLAPPED	EACH	7	7	
* X0321309	CONCRETE PAD	SQ YD	186	186	
* X5017307	PROTECTIVE SHIELD, SPECIAL	SQ YD	35	35	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
X8250505	LIGHTING CONTROLLER, SPECIAL	EACH	1	1	
XX001532	PROJECT SIGN	EACH	2	2	

* SPECIALTY ITEM



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = amandoj
DESIGNED - JDM
DRAWN - JKP
CHECKED - MTC
DATE - 05-07-2012

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2783	11-00253-00-LS	COOK	24	4
CONTRACT NO. 63722			ILLINOIS FED. AID PROJECT	