

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				0021	0021	0021	0021
				FAU 6791	FAU 6801	FAU 6791	FAP 574
				90 FED/10 ST	90 FED/10 ST	90 F/5 ST/5 C	90 F/5 ST/5 C
20200100	EARTH EXCAVATION	CU YD	167.1	167.1			
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	476.5	476.5			
42000546	PORTLAND CEMENT CONCRETE PAVEMENT 12 1/4", JOINTED	SQ YD	332	332			
42400800	DETECTABLE WARNINGS	SQ FT	60	60			
44000100	PAVEMENT REMOVAL	SQ YD	287	287			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	380	380			
44000600	SIDEWALK REMOVAL	SQ FT	422	422			
44003100	MEDIAN REMOVAL	SQ FT	19	19			
44213200	SAW CUTS	FOOT	226.5	226.5			
60605000	COMBINATION CURB AND GUTTER, TYPE B-6. 24 ↑ CONCRETE	FOOT	22	22			
67100100	MOBILIZATION	L SUM	1	1			
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			

URBAN

FILE NAME *
D:\68A98-ehs-105.dgn

USER NAME * ruzinski,jl
PLOT SCALE = 1/8" = 100.0000' / 1" PL
PLOT DATE = 5/23/2012

DESIGNED - JLR
DRAWN - JLR
CHECKED -
DATE - 5/23/2012

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.U. RTE. 6791	SECTION 04 FYA 2012	COUNTY KNOX	TOTAL SHEETS 293	SHEET NO. 13
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68A98	