

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				URBAN			
				0021 FAU 6791 90 FED/10 ST	0021 FAU 6801 90 FED/10 ST	0021 FAU 6791 90 F/5 ST/5 C	0021 FAP 574 90 F/5 ST/5 C
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1				1
87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1				1
87700320	STEEL MAST ARM ASSEMBLY AND POLE, 55 FT.	EACH	1				1
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	41				41
87900200	DRILL EXISTING HANDHOLE	EACH	3				3
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5				5
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10			6	4
88030070	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	5	2			3
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED	EACH	3				3
88200310	TRAFFIC SIGNAL BACKPLATE, LOUVERED, PLASTIC	EACH	19	1		6	12
88600100	DETECTOR LOOP, TYPE 1	FOOT	175			175	
89502105	REBUILD EXISTING SIGNAL HEAD, LED	EACH	56		2	44	10
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	10	1	1	6	2
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1				1

FILE NAME =
D:\68A98\shc-IDS.dgn

USER NAME = rudzinskijl

DESIGNED - JLR

REVISED -

DRAWN - JLR

REVISED -

PLOT SCALE = 100.4566' / in.

CHECKED -

REVISED -

PLOT DATE = 5/23/2012

DATE - 5/23/2012

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6791	D4 FYA 2012	KNOX	29	10
			CONTRACT NO. 68A98	
ILLINOIS FED. AID PROJECT				