

REMOVALS				
LOCATION	PAVEMENT REMOVAL	MEDIAN REMOVAL	CCC&G REMOVAL	SIDEWALK REMOVAL
	SQ YD	SQ FT	FT	FT
US 150 (HENDERSON ST) STA. 492+32 TO STA. 494+21	286.5	9.2	351	
STA 494+ 20			10	147
STA 495+10			13	164
STA 495+ 15		9.6		
STA 495+ 35			6	111
TOTALS	287	19	380	422

STORM SEWER			
LOCATION	REMOVING INLETS	STORM SEWER REMOVAL	INLETS, SPECIAL
	EACH	FT	EACH
STA 493+ 82	2	4	1
TOTALS	2	4	1

PAVEMENT		
STATION	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	PCC PAVEMENT, 12.25"
	SQ YD	SQ YD
HENDERSON ST (US 150) STA 492+42 TO STA 494+21	476.5	332.1
TOTAL	476.5	332.1

CONCRETE ITEMS					
LOCATION	CONCRETE MEDIAN (SPECIAL)	COMB CONC. CURB & GUTTER, TYPE B 6.24	PORTLAND CEMENT CONCRETE SIDEWALK 4" SPECIAL	ISLAND PAVEMENT REMOVAL AND REPLACEMENT	DETECTABLE WARNINGS
	SQ. FT.	FT	SQ. FT.	SQ. FT.	SQ. FT.
US 150 (HENDERSON ST) STA. 492+32 TO STA. 494+07.5	1226.1				
STA 494+ 20		10.2	146.9		10.0
STA 495+10		6.0	164.0		10.0
STA 495+ 15				195.5	30.0
STA 495+ 35		6.0	110.7		10.0
TOTAL	1226	22	422	196	60

EARTHWORK SUMMARY	EARTH EXCAVATION CU. YD.	FOR INFORMATION ONLY		FURNISHED EXCAVATION CU. YD.
		EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (30%) CU. YD.	EMBANKMENT CU. YD.	
STA. 492+32 to 494+07.5	167.1	117.0	0	0.0
Earthwork Total	167			0