

SIDEWALK SCHEDULE

LOCATION STA TO STA	PCC SIDEWALK 5"	DETECTABLE WARNINGS	PROTECTIVE COAT
	SQ FT	SQ FT	SQ YD
IL 13			
EBL			
STA 857+75.0 TO STA 8+40.24 (RUSSELL)	1,340.2		148.9
STA 859+72.8		10.0	
STA 877+22.3		10.0	
STA 877+09.3 TO STA 8+75.46 (HIGHLAND)	1,690.7		187.9
STA 879+80.5		10.0	
STA 880+43.13 TO STA 883+47.9	1,654.9		183.9
STA 880+57.3		10.0	
WBL			
STA 859+12.43 TO STA 11+67.33 (RUSSELL)	963.4		107.0
859+74.25		20.0	
860+81.50		10.0	
STA 860+75.39 TO STA 871+43.01	5,474.3		608.3
871+35.50		10.0	
872+30.25		10.0	
STA 872+18.24 TO STA 876+48.19	2,130.0		236.7
876+36.67		10.0	
STA 877+25.69 TO STA 880+15.53 BK	1,432.7		159.2
877+40.50		10.0	
STA 880+15.69 AH TO STA 883+45.87	1,631.6		181.3
883+37.75		10.0	
STA 883+81.62 TO STA 886+51.99	2,093.3		232.6
883+90.75		10.0	
886+47.10		10.0	
RUSSELL ST.			
STA 8+48.00		10.0	
STA 11+58.50		10.0	
HIGHLAND ST.			
RT STA 9+01.84 TO STA 9+22.86	112.9		13.2
SCHEDULE TOTAL			
	18,524.0	160.0	2,059.0
FROM PCC PAVEMENT SCHEDULE			
			9,154.0
FROM CURB & GUTTER SCHEDULE			
			3,468.0
PROJECT TOTAL			
	18,524	160	14,681