

## SEEDING SCHEDULE

LOCATION STA TO STA	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING
	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE	POUND
<b>IL 13</b>								
EBL								
RT STA 858+00. TO STA 860+00.	0.1	0.1	16.0	12.0	12.0	0.2	0.2	10.0
RT STA 860+64. TO STA 871+54.	0.5	0.5	80.0	60.0	60.0	1.0	1.0	50.0
RT STA 872+00. TO STA 876+66.	0.3	0.3	48.0	36.0	36.0	0.6	0.6	30.0
RT STA 876+93. TO STA 883+40.	0.2	0.2	32.0	24.0	24.0	0.4	0.4	20.0
WBL								
LT STA 858+50. TO STA 860+00.	0.1	0.1	16.00	12.0	12.0	0.2	0.2	10.0
LT STA 860+65. TO STA 871+61.	0.4	0.4	64.00	48.0	48.0	0.8	0.8	40.0
LT STA 872+00. TO STA 876+63.	0.2	0.2	32.00	24.0	24.0	0.4	0.4	20.0
LT STA 877+04. TO STA 883+54.	0.1	0.1	16.00	12.0	12.0	0.2	0.2	10.0
LT STA 883+78. TO STA 886+77.	0.2	0.2	32.00	24.0	24.0	0.4	0.4	20.0
<b>PROJECT TOTAL</b>	<b>2.1</b>	<b>2.1</b>	<b>336</b>	<b>252</b>	<b>252</b>	<b>4.2</b>	<b>4.2</b>	<b>210</b>