

PAVEMENT MARKING SCHEDULE

LOCATION STA TO STA	PERFORMED PAVT. MARKING-TYPE B-INLAID						GROOVING FOR RECESSED PAVT. MARKING							
	LETTERS & SYMBOLS	-LINE 4"			-LINE 12"	- LINE 24"	LETTERS & SYMBOLS	-LINE 5"		-LINE 13"	- LINE 25"			
		WHITE		YELLOW				SOLID	SKIP DASH			SOLID	SOLID	SKIP DASH
		SOLID	SKIP DASH	SOLID										
SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT				
WBL														
STA 858+72.67 TO STA 859+17.43				45.0				45.0						
STA 858+72.67 TO STA 859+48.26					40.0				40.0					
STA 859+75.73 TO STA 860+13.12 PAINTED ISLAND				106.0			77.3	106.0		77.3				
STA 859+89.93 TO STA 860+77.25 PED X-ING				176.0				176.0						
STA 860+60.54 TO STA 860+94.12 PAINTED ISLAND				101.0			46.4	101.0		46.4				
STA 860+79.63											18.0			
STA 860+87.77											48.0			
STA 860+87.77 TO STA 862+76.30				189.0	100.0			189.0	100.0					
STA 860+94.12 TO STA 862+76.30				182.0				182.0						
STA 862+08.50			RT ARROW	15.6				15.6						
RT STA 862+38.14			LT ARROW	15.6				15.6						
STA 862+65.68			"ONLY"	20.8				20.8						
STA 860+76.30 TO STA 863+12.33				36.0										
STA 862+76.30 TO STA 883+25.00					1,040.0									
RT STA 862+95.2			"ONLY"	20.8										
STA 864+51.3 TO STA 871+13.7				663.0				663.0						
LT STA 867+37.8			ARROW	6.5				6.5						
LT STA 867+49.8			BIKE	7.0				7.0						
LT STA 870+81.7			ARROW	6.5				6.5						
LT STA 870+93.7			BIKE	7.0				7.0						
STA 872+34.4 TO STA 873+47.8				114.0										
STA 872+51.45 TO STA 876+14.7				363.0				363.0						
RT STA 872+82.8			LT ARROW	15.6										
RT STA 873+40.0			"ONLY"	20.8										
LT STA 875+82.7			ARROW	6.5				6.5						
LT STA 875+94.7			BIKE	7.0				7.0						
STA 877+30.9 TO STA 880+05.0				274.0										
RT STA 879+21.5			LT ARROW	15.6										
RT STA 879+78.7			"ONLY"	20.8										
STA 880+69.3 TO STA 881+73.4				104.0										
RT STA 881+11.5			LT ARROW	15.6										
RT STA 881+68.7			"ONLY"	21.0										
STA 883+25.0 TO STA 886+11.7					160.0					160.0				
LT STA 883+88.9 TO STA 886+42.7				257.0				257.0						
LT STA 884+88.2			ARROW	6.5				6.5						
LT STA 885+00.2			BIKE	7.0				7.0						
LT STA 886+24.3			ARROW	6.5				6.5						
LT STA 886+36.0			BIKE	7.0				7.0						
STA 886+49.73 TO STA 886+77.33 PAINTED ISLAND				86.0			44.0	86.0		44.0				
STA 886+59.85											18.0			
SHEET 2 SUB TOTALS				249.7	2,696.0	1,340.0	0.0	167.7	84.0	119.5	2,168.0	300.0	167.7	84.0
SHEET 2 TOTALS				249.7		4,036.0		167.7	84.0	119.5		2,468.0	167.7	84.0

NOTES: 1) SEE SHEET 148 FOR DETAIL OF STRAIGHT ARROW AND BIKE SYMBOL.
 2) ALL LEFT AND RIGHT ARROWS ARE LARGE SIZE, "ONLY" LETTERS ARE TO BE 8' IN HEIGHT.

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE - PAVEMENT MARKING 2 OF 3	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pw\work\p\dot\kellaykd\0184451\78203-sht-sched.dgn		DRAWN -	REVISED -			331	(IX-11R-5,RS-3,N-5,TS-4	WILLIAMSON	288	48	
PLOT SCALE = 100.0000' / 1" =		CHECKED -	REVISED -			CONTRACT NO. 78203					
PLOT DATE = 5/11/2012		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
				SCALE:		SHEET NO. OF SHEETS		STA. TO STA.			